



Part I and II (Building and Support Facilities)

This Newsletter Supersedes the Army Facilities Pricing Guide, PAX Newsletter No. 3.2.2, revision dated 30 May 2019, and updates Primary & Support Facilities Unit Cost Tables, Tri-Service Military Construction Program (MCP) Index, and Table-1, Size Adjustment Factors. These costs will be used as a guide for preparation and/or review of Budget Submission of the FY22 Army Military Construction (MCA) and Army Family Housing (AFH) projects' parametric cost estimates and ENG3086s unless otherwise noted. These facility unit costs may not be directly applicable for those facilities that consist of unique requirements. This Newsletter is published and maintained on the web page at:

<http://www.usace.army.mil/CostEngineering/ProgrammingAdministrationandExecutionSystemNE.aspx>

NOTE/Caution: Due to the diminishing number of MILCON projects in the recent years, some guidance unit costs (UC) listed in the 2020 PAX Newsletter are published with less than 3 projects during the recent years due to the significance of those category codes (CatCode) in the upcoming MCA program. UC for those facility types are annotated in the "Remark" column with the number of projects such costs were based on. Users must be aware of this shortcoming if using these UC as guidance unit cost. If accepted by the ENG3086 reviewers and G-9, unit costs developed from similar and awarded projects may be used as a basis.

A. PART-I – PRIMARY FACILITIES UNIT COSTS, dated 20 Mar 20

A.1. The Unit Costs in Part-1 Table represent the cost per square foot as of 1 October 2022 for various CONUS Army facility types (to include projects from Alaska and Hawaii) that were awarded between FY 2017-19 and at least 3 projects per building type were entered into the Historic Analysis Generator (HII) database by 1 Oct 2019. When less than three (3) recent projects were awarded and entered into the HII database between 2016-2019 for a specific facility type (CatCode), then the last four (4) years (2016-2019) projects' data were considered. Only new construction projects located within the Continental United States (CONUS), to include projects in Hawaii and Alaska, were utilized to develop facility specific unit costs, except for Army Family Housing and DoD Schools where OCONUS projects were also considered. Addition-alteration projects, less than 25% of the Standard Reference Size for that facility type, were not included in the database.

A.2. Methodology and Escalation Factor: Facility-specific bid data were normalized to the average number of bidders for that specific facility type, Area Cost Factor of 1.0, Average size for that facility type, and 1 Oct 2019 price level using the actual construction inflation index as obtained from the DoD Selling Price Index. Unit Costs in the PAX Newsletter Table are escalated to 1 Oct 2022. Appendix-C, MCP Index should be used for determining Cost Escalation Factor as shown in the following example for a project with a mid-point of 1 April 2023:

Anticipated Midpoint of Construction for a given project = 1 April 2023

MCP Indexes for 1 Oct 2022 and 1 Apr 2023 from Appendix-C, are 3159 and 3191 respectively

Cost Escalation Factor = 1 Apr 2023 MCP Index / 1 Oct 2022 MCP Index = 3191/3159 = 1.010

A.3. Facilities with PAX Newsletter guidance unit costs are assumed to include the costs of the following features/requirements. Therefore NO Separate Line Item(s) shall be added for the following features:

- a. Minimum antiterrorism design features inside the building, when minimum set back/stand-off distance is achieved.
- b. Progressive Collapse premiums for specific facility types that are normally designed with 3 or more stories, such as Inpatient Hospitals/Medical Centers, Primary Care Clinic (attached), Major Command Headquarters, Barracks/Trainee Barracks, etc.
- c. Building Information Systems (e.g. conduits, racks, trays, telecommunication rooms) for facilities without any Special Communications Requirements.
- d. Energy Management Control System (EMCS) Connections.
- e. Intrusion Detection System (IDS) infrastructure, to include conduits, racks and trays.
- f. Sustainable Design and Development features for criteria in effect from September 2007 thru September 2012 (e.g. LEED Silver Rating, Energy Policy Act of 2005).
- g. Built-in Equipment and furnishings normally funded by MILCON funds,
- h. Standard uncomplicated foundation systems (e.g. Strip/Spread-footings, thickened edge slab for slab on grade). Any Special Foundations, such as Pile Foundations and Structural Fill cost should be listed separately.
- i. Contractor's mark-ups for overhead, and profit.
- j. An average sales tax on building materials.

A.4. PAX Guidance Unit costs do NOT generally include the following feature/requirement costs. Therefore, these costs are to be added as a Separate Line Item(s) in the budget estimate:

- a. Inside the building AT-FP features when minimum stand-off distance cannot be achieved or when enhanced AT-FP features are required due to the height of the building, such as for 3 or more storied buildings when the past designs did not require Progressive Collapse measures. Progressive Collapse premium for 3 or higher storied Standard Designs that have been previously built (e.g., barracks/dormitories) are assumed to be built-into the award data.
- b. Specialized/Secured Building Information System costs.
- c. Sustainable Design and Development features for criteria mandated since September 2013.
- d. Inside the building or Built-in Renewable and alternative Energy features (e.g. ground source heat pumps, roof mounted Solar Panels).
- e. Special Foundation cost (e.g. cost of pre-stressed concrete pile foundation or caissons).
- f. Special Architectural features to comply with the Historic Preservation Guidelines.
- g. Equipment acquired with non-MILCON fund sources (e.g., intrusion detection systems, pre-wired workstations).
- h. Construction Contingency and Supervision, Inspection, and Overhead (SIOH) allowances.
- i. Design-Build Contract Design Cost.
- j. State imposed Gross Receipt Taxes (also referred to as General Exercise Tax).
- k. Construction Cost Growth resulting from Unforeseen Site Conditions, Change Orders, Contract document Errors and/or omissions, or Unusual Market Conditions, such as extreme material or labor shortages at the project location.

A.5. User Generated Unit Costs (UGUC): User Generated Unit costs may be used when PAX UC is not available or when it is not completely applicable for the project. UGUC requires an explanation of how the unit cost was derived.

A.6. Average facility size shown in Part-I, Table may or may not be identical to the size/sizes listed in the Center of Standardization (COS) websites. Table-1, Size Adjustment Factor, which shows correlation between project size and construction cost, should be used to determine the appropriate project cost.

B. PART-II – SUPPORT FACILITIES UNIT COSTS, dated 20 Mar 2020

B.1. Support Facilities unit costs are based upon National Average Davis Bacon wages and material pricing. The Area Cost Factor (ACF) for this database is 1.0. Support Facility unit costs should be adjusted for the project location only when guidance unit costs are used; when local cost data (user generated cost data) is used, no ACF adjustments should be made.

B.2. All pricing includes the installing contractor's Overhead and Profit (O&P). General Contractor's mark-up is not included. The installing contractor's O&P includes the following factors:

- a. Employees wage rate and fringe benefits
- b. Workmen's compensation insurance
- c. Social Security and Federal and State Unemployment taxes
- d. Contractor's Overhead (11%) and Profit (10%)
- e. Data incorporates an average 6% Sales Tax.

B.3 Points of contact for this Newsletter at the US Army Corps of Engineers are: Ms. Tracy Leeser (HQUSACE), (202) 761 7750, e-mail: Tracy.T.Leeser@usace.army.mil and alternate POC, Mr. Bryan Simpkins (CEHNC-EDS-C), (256) 895 5505, e-mail: Bryan.Simpkins@usace.army.mil

Facility Unit Costs (UC) are average unit costs based on the most Recent 4-Year (2016-19) project awards per building type.

All UC's are the average unit costs for new construction, escalated to 1 Oct 2022, using the Inflation Guidance for

FY 2021 President's Budget, 3 April 2019 and Normalized to an Area Cost Factor of 1. Please refer to the "Notes" in the Remarks Column of Table.

CAT CODE	Description	Facility Average or Standard Size	Unit Of Measure (UoM)	FY22 Unit Cost (\$ / UoM)	Remarks
					Note-1: No data or Not enough useable Army Bid Data since 2016 to forecast UC. Note-2: Last year's unit cost (UC) escalated 1 year. Not enough projects awarded to forecast UC. Note-3: UC & Ref Size based on GUC / DOD / TriService Guidance.
13115	Information Systems Facility	XX	SF	XX	See Note-1. Insufficient recent cost data.
	Houses majority of Garrison level Info Management & Info Tech services plus associated admin Support & shop spaces.				
13120	Communications Center	36,000	SF	559.00	See Note-3: UC & Ref Size based on GUC / DOD Guidance.
	Hub facility for Internal & External Communications, commercial telephone feeds, and environmental control requirements; DSN switching equipment. No shielding included.				
13120	Remote Switching Unit (RSU)	XX	SF	XX	See Note-1. Insufficient recent cost data.
13131	Information Processing Center	XX	SF	XX	See Note-1. Insufficient recent cost data.
	Also called Data processing Ctr. Houses personnel & equipment for data-processing; special temp, humidity, environmental control requirements, raised floor and security measures.				
13181	Satellite Terminal Communications Facility	XX	SF	XX	See Note-1. Insufficient recent cost data.
13310	Air Traffic/ Flight Control Tower	XX	SF	XX	See Note-1. Insufficient recent cost data.
14110	Airfield Operations (Ops) Building	XX	SF	XX	See Note-1. Insufficient recent cost data.
	Houses flight operations and Airfield HQ functions with or w/o Flight Control Tower.				
14112	Aviation Unit Ops Bldg at Airfield	35,000	SF	299.00	Note-3: UC & Ref Size based on GUC / DOD / TriService Guidance.
	Houses Aviation Unit HQ admin, training, and storage area.				
14113	Access Control Facility - Mission Trng Complex	XX	SF	XX	See Note-1. Insufficient recent cost data.
14113	Access Control Facility (ACF) Complex (Reference Sizes are the Average size of reported projects in each CATCD)				
	Visitors Control Center	2,960	SF	408.00	Ref size & UC based on project data in HII Published w/1 Omaha COS approved data point.
	Search Office/ Sentry Building	660	SF	520.00	Ref size & UC based on project data in HII Published w/1 Omaha COS approved data point.
	Gatehouse	933	SF	731.00	Ref size & UC based on project data in HII Published w/1 Omaha COS approved data point.
	Guard booth (Also called Guardhouse)	40	SF	1,533.00	Last year's unit cost (UC) escalated 1 year. Not enough projects awarded to forecast UC.
	Overwatch Guard Booth	36	SF	2,202.00	Ref size & UC based on project data in HII Published w/1 Omaha COS approved data point.
	POV Search Canopy	1,530	SF	160.00	Ref size & UC based on project data in HII Published w/1 Omaha COS approved data point.
	I.D. Check Area Canopy	9,152	SF	133.00	Ref size & UC based on project data in HII Published w/1 Omaha COS approved data point.
	Search Area Canopy - Truck	4,000	SF	295.00	Ref size & UC based on project data in HII Published w/1 Omaha COS approved data point.
14114	CIDC Field Operations Bldg	5,727	SF	571.00	Ref size & UC based on project data in HII Published w/1 Omaha COS approved data point.
14126	Kennel Facilities	XX	SF	XX	See Note-1. Insufficient recent cost data.
14129	Training Aid Spt Ctr for Range Complex	XX	SF	XX	See Note-1. Insufficient recent cost data.
14132	Ready Building-Airfield Arrival/Depart Control Fac	XX	SF	XX	See Note-1. Insufficient recent cost data.
14161	Emergency Operations Ctr (EOC)	XX	SF	XX	See Note-1. Insufficient recent cost data.
14162	Sensitive Compartmented Info Fac (SCIF)	XX	SF	XX	See Note-1. Insufficient recent cost data.
14165	Vehicle Maintenance Wash Facility: Consists of Wash Bays, Prewash Control, Pump House, Grit & Oil Chambers,				
	Control Bld for Vehicle Wash Rack	XX	SF	XX	See Note-1. Insufficient recent cost data.
	Pump Bld for Vehicle Wash Rack	XX	SF	XX	See Note-1. Insufficient recent cost data.
	Gravity Oil & Grease Separator	XX	KGD	XX	See Note-1. Insufficient recent cost data.
	Water & Grit Separator	XX	KGD	XX	See Note-1. Insufficient recent cost data.
14179	Overhead Protection/Canopy - General	XX	SF	XX	see CC 14179 for Covered Hardstand (Canopy) under COF below
14182	Brigade (BDE) Headquarters Bldg	XX	SF	XX	See Note-1. Insufficient recent cost data.
	Use Size Adj Table-1, Part-1 to determine unit cost for other sizes (Small , Medium and X-Large) BDE HQs. UC does Not include new SCIF reqm cost				
14183	Battalion (BN) HQ Bldg w/Classrooms	76,000	SF	321.00	Note-3: UC & Ref Size based on GUC / DOD / TriService Guidance.
	Use Size Adj Table-1, Part-1 to determine unit cost for other sizes (Small, Large and X-Large BN HQs				
	BN HQ - Transient Training (ORTC)	XX	SF	XX	See Note-1. Insufficient recent cost data.

Facility Unit Costs (UC) are average unit costs based on the most Recent 4-Year (2016-19) project awards per building type.					
All UC's are the average unit costs for new construction, escalated to 1 Oct 2022, using the Inflation Guidance for					
FY 2021 President's Budget, 3 April 2019 and Normalized to an Area Cost Factor of 1. Please refer to the "Notes" in the Remarks Column of Table.					
CAT CODE	Description	Facility Average or Standard Size	Unit Of Measure (UoM)	FY22 Unit Cost (\$ / UoM)	Remarks
14185	COMPANY OPERATIONS FACILITY (COF)				COF Ref Size varies based on AM & RM configuration
	Admin & Readiness Modules are usually combined for small 1-Company (150 soldiers) or 2-CO (300 soldiers @150 PN/Company Units. For larger COFs, i.e., 3 or more companies, Admin (AM) and Readiness Modules (RM) are normally detached. RM storage space is fully conditioned and sprinklered for TA-50 Lockers and Arms Vault.				
	The cost of contractor furnished and installed TA 50 Lockers are included in the UC. Admin and Readiness Modules may be programmed separately in DD1391/ENG3086				
14185	Admin/Readiness - Integrated Module	40,823	SF	346.00	Ref size & UC based on project data in HII Published w/1 Savannah COS approved data point.
14185	Admin Module (AM) - Detached	XX	SF	XX	See Note-1. Insufficient recent cost data.
14185	Readiness Module (RM) - Detached	XX	SF	XX	See Note-1. Insufficient recent cost data.
14179	Canopy for Covered Hardstand (Not Enclosed)	XX	SF	XX	See Note-1. Insufficient recent cost data.
	Includes the cost of Canopy, supporting posts, their foundations and Hardstand cost. COF overhead protection is a Pre-engineered structure w/lighting & lightning protection over the equipment layout.				
14179	Enclosed Hardstand (for extreme climates)	XX	SF	XX	See Note-1. Insufficient recent cost data.
14190	Command & Control Fac (C2F)	110,000	SF	434.00	Note-3: UC & Ref Size based on GUC / DOD / TriService Guidance.
	Division and Corps Level Command & Control Bld for a all service components. C2F Bld contains 3 distinct functional elements, Admin, Emergency Network Operation, and SCIF spaces (does Not include new SCIF reqm cost) The costs of raised flooring, redundant electrical/mechanical systems, and secured access system are included.				
	C2F Bldg above Corps level is a non-standard facility.				
14190	Army Command (ACOM) Headquarters	130,000	SF	481.00	See Note-3: UC & Ref Size based on GUC / DOD Guidance.
14955	Wash Rack / Platform - Army Reserve Centers	1,577	SF	168.00	Use for 1001-1600 SF Wash Racks. Based on 2 Army Reserve Center projects Approved by Louisville COS.
14960	Grease Rack - Low Pressure w/Wash Water Treatment	XX	EA	XX	See Note-1. Insufficient recent cost data.
14962	Central Wash Facility, 16 Stations	XX	EA	XX	See Note-1. Insufficient recent cost data.
14970	Bi-Level Loading Ramp, Army Reserve Centers	1	EA	165,116.00	Ref size & UC based on project data in HII Published w/1 Louisville COS approved data point.
14970	Single Level Loading Ramp, Army Reserve Centers	1	EA	82,100.00	Last year's unit cost (UC) escalated 1 year. Not enough projects awarded to forecast UC.
14970	Ammo Loading Dock for Range	XX	EA	XX	See Note-1. Insufficient recent cost data.
14970	Vehicle Instrumentation Dock, 900 SF	XX	EA	XX	See Note-1. Insufficient recent cost data.
17120	General Instruction Bldg (GIB) & Total Army School (TASS) - Not for Range	45,670	SF	274.00	Ref size & UC based on project data in HII Published w/1 Norfolk COS approved data point.
	RANGE FACILITIES COMPLEX				
	A typical Range Complex consists of Target Emplacements/Firing Points, Range Ops and Control Area, and a number of vertical structures, such as, Control Tower, Range Ops & Storage Bld, Range Classroom Bld, Ammo Breakdown Bld, Field Latrines				
	plus other covered (but not enclosed) structures, e.g. Covered Bleachers, Covered Mess, etc.				
14113	Access Control Fac - Mission Trng Complex	XX	SF	XX	See Note-1. Insufficient recent cost data.
14129	Training Aid / Support Center (TSC)	XX	SF	XX	See Note-1. Insufficient recent cost data.
14970	Ammunition Loading Dock - Single Level for Ranges	1	EA	89,479.00	Last year's unit cost (UC) escalated 1 year. Not enough projects awarded to forecast UC.
14970	Loading Dock - Bi-Level for Army Reserve Centers	1	EA	165,116.00	Ref size & UC based on project data in HII Published w/1 Louisville COS approved data points.
17121	Indoor Firing Range	34,000	SF	312.00	See Note-3: UC & Ref Size based on GUC / DOD Guidance.
17122	Ammunition Breakdown Bldg	185	SF	973.00	Ref size & UC based on project data in HII Published w/2 Huntsville COS approved data point.
17122	Operations/Storage Bld - Small	800	SF	386.00	Ref size & UC based on project data in HII Published w/2 Huntsville COS approved data point.
17122	Operations/Storage Bld - Large	XX	SF	XX	See Note-1. Insufficient recent cost data.
17123	Range Classroom Building	800	SF	345.00	Ref size & UC based on project data in HII Published w/2 Huntsville COS approved data point.
17123	After Action Review (AAR) Bld - Small	XX	SF	XX	See Note-1. Insufficient recent cost data.
17123	After Action Review (AAR) Bld - Large	3,090	SF	286.00	Last year's unit cost (UC) escalated 1 year. Not enough projects awarded to forecast UC.

Facility Unit Costs (UC) are average unit costs based on the most Recent 4-Year (2016-19) project awards per building type. All UC's are the average unit costs for new construction, escalated to 1 Oct 2022, using the Inflation Guidance for FY 2021 President's Budget, 3 April 2019 and Normalized to an Area Cost Factor of 1. Please refer to the "Notes" in the Remarks Column of Table.					
CAT CODE	Description	Facility Average or Standard Size	Unit Of Measure (UoM)	FY22 Unit Cost (\$ / UoM)	Remarks
17123	Combined ROC/AAR-Digital Range	XX	XX	XX	See Note-1. Insufficient recent cost data.
17139	Covered Mess - Range (Small)	800	SF	221.00	Includes hardstand cost below canopy. Ref size & UC based on project data in HII Published w/ 1 Huntsville COS approved data point.
17139	Covered Mess - Range (Large)	XX	XX	XX	See Note-1. Insufficient recent cost data.
17139	Covered Mess - Service Schools	XX	XX	XX	See Note-1. Insufficient recent cost data.
17213	Mission Command Trng Center (formerly BCTC)	52,000	SF	433.00	Note-3: UC & Ref Size based on GUC / DOD / TriService Guidance.
17801	Basic 10-25m Firing Range (Zero)	FP	EA	Site Specific	Requires 32 Firing Points (FP)
17805	Automated Record Fire Range	FP	EA	Site Specific	Requires 16 FPs
17806	Modified Record Fire Range	FP	EA	XX	See Note-1. Insufficient recent cost data.
17821	Combat Pistol/MP Firearms Qualifications	FP	EA	Site Specific	Requires 15 FPs
17878	Urban Assault Course	FP	EA	Site Specific	Requires 5 Stations. Each station represents one FP
17879	Live Fire Exercise Shoot house	FP	EA	Site Specific	Requires 10 FPs, each room and Corridor equals 1 FP
	Range Control Towers (RCT)				
	Open Observation decks, stairs, and walkways are calculated as half areas. Foundation cost is included in the Unit Cost.				
17971	Control Tower - Standard Instrumented	1	EA	716,043.00	Ref size & UC based on project data in HII Published w/1 Huntsville COS approved data point.
17971	Control Tower - Standard Small Arms	1	EA	498,582.00	Ref size & UC based on project data in HII Published w/2 Huntsville COS approved data point.
73075	Field Latrine - Dry Type, Aerated Vault	330	SF	517.00	Ref size & UC based on project data in HII Published w/1 Huntsville COS approved data point.
73075	Field Latrine -Wet Closet	550	SF	1217.00	Ref size & UC based on project data in HII Published w/1 Huntsville COS approved data point.
75061	Covered Bleacher - Range (Bleacher Enclosure)	1	EA	211,562.00	Ref size & UC based on project data in HII Published w/1 Huntsville COS approved data points.
75061	Covered Bleacher for Svc Schools	XX	EA	XX	See Note-1. Insufficient recent cost data.
17133	Vehicle Maint. Instructional Bldg	XX	SF	XX	See Note-1. Insufficient recent cost data.
17134	Aircraft Maint Instructional Bldg	XX	SF	XX	See Note-1. Insufficient recent cost data.
17135	Laboratory Instructions Bldg	XX	SF	XX	See Note-1. Insufficient recent cost data.
17136	Automation Aided Instruction Bldg	XX	SF	XX	See Note-1. Insufficient recent cost data.
17137	Material Handling Instructional Bldg	XX	SF	XX	See Note-1. Insufficient recent cost data.
	<u>ARMY RESERVE CTR COMPLEX</u>				
17140	Training Bldg - Army Reserve (Army Res Ctr Bldg) (All)	49,000	SF	341.00	Note-3: UC & Ref Size based on GUC / DOD / TriService Guidance.
17140	Training Bldg - Army Reserve (Army Res Ctr Bldg) (w/Kitchen)	60,458	SF	315.00	Ref size & UC based on project data in HII Published w/4 Louisville COS approved data points.
17140	Training Bldg - Army Reserve (Army Res Ctr Bldg) (wo/Kitchen)	47,189	SF	319.00	Ref size & UC based on project data in HII Published w/2 Louisville COS approved data points.
17211	Simulator Building - Army Reserve	1,800	SF	482.00	Note-2: Last year's unit cost (UC) escalated 1 year. Not enough projects awarded to forecast UC.
14970	Loading Dock, Bi-Level (Also called Loading Ramp)	1	EA	165,116.00	Ref size & UC based on project data in HII Published w/1 Louisville COS approved data points.
21409	Organizational Maintenance Shop (OMS)	6,700	SF	384.00	Note-2: Last year's unit cost (UC) escalated 1 year. Not enough projects awarded to forecast UC.
44220	Storage Building, Unheated	3,450	SF	133.00	Ref size & UC based on project data in HII Published w/8 Louisville COS approved data points.
17211	Simulator Building, Small <18,000 SF	1,800	SF	482.00	Note-2: Last year's unit cost (UC) escalated 1 year. Not enough projects awarded to forecast UC.
17211	Simulator Building, Large >18,000 SF	XX	SF	XX	See Note-1. Insufficient recent cost data.
17971	Control/Observation Tower	XX	EA	See Range	See CATCD 17971 under Range Complex above

Facility Unit Costs (UC) are average unit costs based on the most Recent 4-Year (2016-19) project awards per building type.

All UC's are the average unit costs for new construction, escalated to 1 Oct 2022, using the Inflation Guidance for

FY 2021 President's Budget, 3 April 2019 and Normalized to an Area Cost Factor of 1. Please refer to the "Notes" in the Remarks Column of Table.

CAT CODE	Description	Facility Average or Standard Size	Unit Of Measure (UoM)	FY22 Unit Cost (\$ / UoM)	Remarks
	<u>AIRCRAFT (AC) MAINT HANGARS - DOD, reference only</u>				
21110	Hangar - General Purpose, up to 40' high	100,000	SF	416.00	See Note-3: UC & Ref Size based on GUC / DOD Guidance.
21110	Hangar - High Bay, >40' high	116,650	SF	385.00	Ref size & UC based on project data in HII Published w/ 1 Mobile COS approved data point.
	<u>ARMY HANGAR STANDARDS - Manned and Unmanned Army Hangar Facilities</u>				
	Army Standard Hangars include High Bay Maintenance area, Allied Shops, Tech Supply, Tool Storage, Flight Operations and Company Administrative & Supply spaces.				
21110	Assault / Attack - Reconnaissance (AAB) BN Hangar	113,500	SF	343.00	Note-2: Last year's unit cost (UC) escalated 1 year. Not enough projects awarded to forecast UC.
21110	General Support Aviation BN (GSAB) Hangar	143,600	SF	351.00	Note-2: Last year's unit cost (UC) escalated 1 year. Not enough projects awarded to forecast UC.
21110	Aviation Support Aviation BN (ASB) Hangar	XX	SF	XX	See Note-1. Insufficient recent cost data.
21115	Unmanned Aerial System (UAS) Hangar	58,000	SF	220.00	Ref size & UC based on project data in HII Published w/ 1 Mobile COS approved data points.
21117	Aircraft Electronic - Avionics Maint Shop	XX	SF	XX	See Note-1. Insufficient recent cost data.
21120	Aircraft Component Repair Shop (Machine Shop)	XX	SF	XX	See Note-1. Insufficient recent cost data.
21130	Aircraft Paint / Corrosion Control Shop	100,000	SF	452.00	See Note-3: UC & Ref Size based on GUC / DOD Guidance.
21140	Aircraft Engine Test facility	XX	SF	XX	See Note-1. Insufficient recent cost data.
	<u>TACTICAL EQUIPMENT MAINT FACILITY (TEMF) COMPLEX For Track & Wheeled Vehicles</u>				
	TEMF Complex includes Admin space, Repair & Maintenance shops and work-bays w/ overhead crane, arms/COMSEC vault Storage areas, Deployment Storage bldg, POL Storage bldg, Tactical Vehicle Parking Apron, and Hazard Waste Storage area.				
	<u>ORGANIZATIONAL MAINT SHOP - ARMY RESERVE</u>				
21409	Organizational Maint Shop, Small <10,000 SF	5,368	SF	354.00	Ref size & UC based on project data in HII Published w/ 3 Louisville COS approved data points.
21409	Organizational Maint Shop, Medium 10,000 - 40,000 SF	12,421	SF	325.00	Ref size & UC based on project data in HII Published w/ 2 Louisville COS approved data points.
21409	Organizational Maint Shop, Large, >40,000 SF	92,221	SF	306.00	Ref size & UC based on project data in HII Published w/ 1 Louisville COS approved data point.
	<u>ORGANIZATIONAL MAINT SHOP - REGULAR ARMY</u>				
21410	TEMF, Small - Army, Regular, <21,000 SF	8,000	SF	404.00	See Note-3: UC & Ref Size based on GUC / DOD Guidance.
21410	TEMF, Medium - Army, Regular, >21,000 SF	XX	SF	XX	See Note-1. Insufficient recent cost data.
21410	TEMF, Large - Army, Regular	54,879	SF	282.00	Ref size & UC based on project data in HII Published w/ 1 Savannah COS approved data point.
21410	TEMF, Extra Large - Army, Regular, >60,000 SF	XX	SF	XX	See Note-1. Insufficient recent cost data.
21412	Unmanned Aerial Vehicle (UAV) Storage Bld, 18' high	XX	SF	XX	See Note-1. Insufficient recent cost data.
21470	POL Storage Bldg - TEMF	373	SF	368.00	Ref size & UC based on project data in HII Published w/ 3 Savannah COS approved data points.
21470	Hazardous Waste Storage Bldg - TEMF	380	SF	387.00	Ref size & UC based on project data in HII Published w/ 2 Savannah COS approved data points.
44135	Hazardous Material Storage Bldg - TEMF	XX	SF	XX	Use the same UC as CATCD 21470 above
44220	Storage Bldg - Small, Unheated - Army Reserve	XX	SF	XX	See CATCD 44220 under ARCC
44222	Storage Shed (Covered, not Enclosed), ORTC	2,250	SF	77.00	Note-2: Last year's unit cost (UC) escalated 1 year. Not enough projects awarded to forecast UC.
21412	Organizational Storage Bldg - TEMF, < 5,000 SF	XX	SF	XX	See Note-1. Insufficient recent cost data.
21412	Organizational Storage Bldg - TEMF, > 5,000 SF	XX	SF	XX	See Note-1. Insufficient recent cost data.
21610	Ammunition Renovation Shop	XX	SF	XX	See Note-1. Insufficient recent cost data.
21612	Ammunition Surveillance Shop	XX	SF	XX	See Note-1. Insufficient recent cost data.
21630	Ammunition Demilitarization Fac	XX	SF	XX	See Note-1. Insufficient recent cost data.
21710	Electronics Maint Shop - Depot Level	XX	SF	XX	See Note-1. Insufficient recent cost data.

Facility Unit Costs (UC) are average unit costs based on the most Recent 4-Year (2016-19) project awards per building type.

All UC's are the average unit costs for new construction, escalated to 1 Oct 2022, using the Inflation Guidance for

FY 2021 President's Budget, 3 April 2019 and Normalized to an Area Cost Factor of 1. Please refer to the "Notes" in the Remarks Column of Table.

CAT CODE	Description	Facility Average or Standard Size	Unit Of Measure (UoM)	FY22 Unit Cost (\$ / UoM)	Remarks
					Note-1: No data or Not enough useable Army Bid Data since 2016 to forecast UC. Note-2: Last year's unit cost (UC) escalated 1 year. Not enough projects awarded to forecast UC. Note-3: UC & Ref Size based on GUC / DOD / TriService Guidance.
21740	Aircraft Avionics Maint Shop	XX	SF	XX	See Avionics Maint Shop, CATCD 21117 Remarks above
21850	Battery Shop	600	SF	294.00	Ref size & UC based on project data in HII Published w/ 1 Huntsville COS approved data point.
21881	Parachute Repair Shop	XX	SF	XX	See Note-1. Insufficient recent cost data.
21885	General Purpose Maint Shop	XX	SF	XX	See Eng/Housing Maint Shop, CATCD 21910 UC below
21910	Engineering / Housing Maint Shop	XX	SF	XX	See Note-1. Insufficient recent cost data.
31010	Chemistry Lab	XX	SF	XX	See Note-1. Insufficient recent cost data.
31410	Ground Transportation Equip Bldg	XX	SF	XX	See Note-1. Insufficient recent cost data.
42120	Hi Explosive Magazine w/Crane	9,200	SF	616.00	See Note-3: UC & Ref Size based on GUC / DOD Guidance.
42180	Igloo Storage, Depot Level	XX	SF	XX	See Note-1. Use same UC as in CC42120 above
42183	Gen. Purpose Magazine w/o Crane	XX	SF	XX	See Note-1. Insufficient recent cost data.
42283	Gen Purpose Magazine w/o Crane - Installation	XX	SF	XX	See Note-1. Insufficient recent cost data.
43211	Cold Storage Bld w/Processing	XX	SF	XX	See Note-1. Insufficient recent cost data.
43211	Cold Storage Bld w/o Processing	XX	SF	XX	See Note-1. Insufficient recent cost data.
44110	General Purpose (GP) Warehouse, Depot		SF		See CATCD 44220 below
44130	Controlled Humidity Warehouse	XX	SF	XX	See Note-1. Insufficient recent cost data.
44135	Hazardous Material Storage, Depot	XX	SF	XX	See Note-1. Insufficient recent cost data.
44150	Flammable Material Storage, Depot	XX	SF	XX	See Note-1. Insufficient recent cost data.
44181	Covered Vehicle Storage, Depot	XX	SF	XX	See Note-1. Insufficient recent cost data.
44182	Vehicle Storage Building, Depot	XX	SF	XX	See Note-1. Insufficient recent cost data.
44210	Aircraft Parts Storage Fac, Installation	XX	SF	XX	See Note-1. Insufficient recent cost data.
44220	Gen Purpose (GP) Warehouse, Installation				
44220	Low-Bay, Up to 16' Stack height, <15,000 SF	7,100	SF	201.00	See Note-3: UC & Ref Size based on GUC / DOD Guidance.
44220	Low-Bay, Up to 16' Stack height, >15,000 SF	28,000	SF	198.00	See Note-3: UC & Ref Size based on GUC / DOD Guidance.
44220	Hi-Bay, > 16' Clear Stack height	XX	SF	XX	See Note-1. Insufficient recent cost data.
44220	Lawn Equipment Bldg for AIT/BT barracks	XX	SF	XX	See Note-1. Insufficient recent cost data.
44220	Unheated Storage Bldg - Army Reserve	5,327	SF	107.00	Ref size & UC based on project data in HII Published w/7 Louisville COS approved data points.
44222	Storage Shed (Covered, not Enclosed) - Small	2,250	SF	77.00	Note-2: Last year's unit cost (UC) escalated 1 year. Not enough projects awarded to forecast UC.
21412	Organizational Equipment Storage Bldg	XX	SF	XX	See Note-1. Insufficient recent cost data.
	For COF Equip. Storage UC, see Readiness Module - CC14185				
44224	Organizational Storage Bldg	2,100	SF	407.00	Note-2: Last year's unit cost (UC) escalated 1 year. Not enough projects awarded to forecast UC.
44224	Lawn Mower Storage Bldg for AIT/BT barracks	XX	SF	XX	See Note-1. Insufficient recent cost data.
44228	HAZMAT Storage - Installation	XX	SF	See CC21470	Use the same UC as CATCD 21470
45210	Open Storage Area - Installation	XX	SY	XX	Use CATCD 851XX, Pavements, from Part-II, PAX
	MEDICAL FACILITIES				
51010	Inpatient Hospital / Medical Center	XX	SF	XX	See Note-1. Insufficient recent cost data.
51010	Medical Clinic attached to Hospital	XX	SF	XX	See Note-1. Insufficient recent cost data.
53040	Veterinary Clinic	XX	SF	XX	See Note-1. Insufficient recent cost data.
55010	Small Medical Clinic <60,000 SF, Free Standing	39,000	SF	464.00	See Note-3: UC & Ref Size based on GUC / DOD Guidance.
55010	Large Medical Clinic >60,000 SF, Free Standing	120,000	SF	382.00	See Note-3: UC & Ref Size based on GUC / DOD Guidance.
55010	Mental / Behavioral Health Clinic	XX	SF	XX	See Note-1. Insufficient recent cost data.
54010	Dental Clinic	XX	SF	XX	See Note-1. Insufficient recent cost data.

Facility Unit Costs (UC) are average unit costs based on the most Recent 4-Year (2016-19) project awards per building type.

All UC's are the average unit costs for new construction, escalated to 1 Oct 2022, using the Inflation Guidance for

FY 2021 President's Budget, 3 April 2019 and Normalized to an Area Cost Factor of 1. Please refer to the "Notes" in the Remarks Column of Table.

CAT CODE	Description	Facility Average or Standard Size	Unit Of Measure (UoM)	FY22 Unit Cost (\$ / UoM)	Remarks
					Note-1: No data or Not enough useable Army Bid Data since 2016 to forecast UC. Note-2: Last year's unit cost (UC) escalated 1 year. Not enough projects awarded to forecast UC. Note-3: UC & Ref Size based on GUC / DOD / TriService Guidance.
53025	Satellite Pharmacy	XX	SF	XX	See Note-1. Insufficient recent cost data.
53060	Medical Warehouse	XX	SF	XX	See Note-1. Insufficient recent cost data.
53071	Ambulance Garage	XX	SF	XX	See Note-1. Insufficient recent cost data.
61001	Military Entrance Processing Stn	XX	SF	XX	See Note-1. Insufficient recent cost data.
61050	Administrative Fac, General Purpose				
	This multipurpose building provided office space, visitors area, auditorium, cafeteria, storage space, etc for administrative personnel				
61050	Administrative Fac, General Purpose, Small	XX	SF	XX	See Note-1. Insufficient recent cost data.
61050	Administrative Fac, General Purpose, Medium	XX	SF	XX	See Note-1. Insufficient recent cost data.
61050	Administrative Fac, General Purpose, Large	XX	SF	XX	See Note-1. Insufficient recent cost data.
	Prewired work station @ \$4,500/Stn installed, NOT included				
61050	Command Headquarters Bldg	XX	SF	XX	New CATCD 14190, see CC14190 for UC
62010	Underground Administrative Facility	XX	SF	XX	See Note-1. Insufficient recent cost data.
ARMY FAMILY HOUSING DWELLINGS - CONUS & OCONUS (Contact Family Housing COS, CENAO for determining additional planning factors for multi-family dwellings.)					
Show "Families (FA)" as the UOM in the in the Primary Line item by category code. Use SF per Family as the UOM in Subline item. Don't need to size adjust the UC per SF					
(using the Size Adj Table-, Part-I) as the adjusted unit cost per FA by catcode, grade, and number of bedroom/per dwelling is already provided in the UC column below.					
Use Size Adj Table-1, Part - II only for project size adj. Normally 2-car garage (400 SF) cost is provided with each dwelling. GSF of garage is not included in the dwelling GSF, but cost of					
garage is considered included in the AFH unit cost as a norm. (i) Add up to 300 SF/FA for harsh climates, defined as having more than 7,500 Heating Degree Days (HDD) annually,					
or 5,500 Cooling Degree Days (CHD), annually. (ii) Gross SF may be increased by 10% FA for housing units for an officer holding a special command position, for the commanding officer					
of a military installation, and for the senior non-commissioned officer of a military installation.					
	<u>ARMY FAMILY HOUSING DWELLINGS</u>	Size	Family Unit & SF	CONUS / OCONUS	
71111	General Officer, Grade O10, 4 Bedrooms	4,000	SF / FA	248.00 / 282.00	
71111	General Officer, Grade O9, 4 Bedrooms	4,000	SF / FA	248.00 / 282.00	
71111	General Officer, Grade O8, 4 Bedrooms	3,300	SF / FA	251.00 / 285.00	
71111	General Officer, Grade O7, 4 Bedrooms	3,300	SF / FA	251.00 / 285.00	
71112	Colonel, Grade O6, 4 Bedrooms	2,520	SF / FA	246.00 / 272.00	
71113	Warrant Officer, Grade W4 & W5, 3 Bedrooms	2,020	SF / FA	233.00 / 266.00	
71113	Warrant Officer, Grade W4 & W5, 4 Bedrooms	2,310	SF / FA	232.00 / 265.00	
71113	LT. Colonel & Major, Grade O4 & O5, 3 Bedrooms	2,020	SF / FA	233.00 / 266.00	
71113	LT. Colonel & Major, Grade O4 & O5, 4 Bedrooms	2,310	SF / FA	232.00 / 265.00	

Facility Unit Costs (UC) are average unit costs based on the most Recent 4-Year (2016-19) project awards per building type.					
All UC's are the average unit costs for new construction, escalated to 1 Oct 2022, using the Inflation Guidance for					
FY 2021 President's Budget, 3 April 2019 and Normalized to an Area Cost Factor of 1. Please refer to the "Notes" in the Remarks Column of Table.					
CAT CODE	Description	Facility Average or Standard Size	Unit Of Measure (UoM)	FY22 Unit Cost (\$ / UoM)	Remarks
					Note-1: No data or Not enough useable Army Bid Data since 2016 to forecast UC. Note-2: Last year's unit cost (UC) escalated 1 year. Not enough projects awarded to forecast UC. Note-3: UC & Ref Size based on GUC / DOD / TriService Guidance.
71114	Warrant Officer, Grade W1-W3, 3 Bedrooms	1,860	SF / FA	213.00 / 245.00	
71114	Warrant Officer, Grade W1-W3, 4 Bedrooms	2,150	SF / FA	210.00 / 241.00	
71114	Warrant Officer, Grade W1-W3, 5 Bedrooms	2,510	SF / FA	206.00 / 239.00	
71114	CO Grade Officer, O1-O3, 3 Bedrooms	1,860	SF / FA	213.00 / 245.00	
71114	CO Grade Officer, O1-O3, 4 Bedrooms	2,150	SF / FA	210.00 / 241.00	
71114	CO Grade Officer, O1-O3, 5 Bedrooms	2,510	SF / FA	206.00 / 239.00	
71115	Senior NCO, E-9, 3 Bedrooms	2,020	SF / FA	244.00 / 266.00	
71115	Senior NCO, E-9, 4 Bedrooms	2,310	SF / FA	232.00 / 265.00	
71115	Senior NCO, E-7 & E-8, 3 Bedrooms	1,860	SF / FA	213.00 / 245.00	
71115	Senior NCO, E-7 & E-8, 4 Bedrooms	2,150	SF / FA	210.00 / 241.00	
71115	Senior NCO, E-7 & E-8, 5 Bedrooms	2,510	SF / FA	206.00 / 239.00	
71116	Junior NCO/Enlisted, E-1 thru E-6, 3 Bedrooms	1,630	SF / FA	218.00 / 250.00	
71116	Junior NCO/Enlisted, E-1 thru E-6, 4 Bedrooms	1,950	SF / FA	215.00 / 246.00	
71116	Junior NCO/Enlisted, E-1 thru E-6, 5 Bedrooms	2,300	SF / FA	211.00 / 243.00	
	<u>GARAGE & CARPORTS</u>				
71410	Detached Garage, Masonry, 2-Car	XX	SF	XX	See Note-1. Insufficient recent cost data.
71410	Detached Garage, Wood, 2-Car	XX	SF	XX	See Note-1. Insufficient recent cost data.
71411	Carport - 2 Cars	XX	SF	XX	See Note-1. Insufficient recent cost data.
85218	Parking Garage, Multistoried	XX	SF	XX	UC provided under CATCD 85218 below.
72010	Temporary Lodging	XX	SF	XX	See CATCD 72412 also called Transient Housing.
72111	BARRACKS - Permanent Party (UEPH)	73,000	SF	398.00	Note-3: UC & Ref Size based on GUC / DOD / TriService Guidance.
	Unit cost does not include the cost for free standing equipment. All finished or unfinished areas with an average height of 6'-11" (2100 mm), measured from the underside of the structural system, and areas with perimeter walls measuring 4'-11" (155 mm) or more shall be counted as full scope				
Various	<u>WARRIORS IN TRANSITION (WT) BARRACKS COMPLEX</u>				
72112	WT Barracks, 56 Person Module	XX	SF	XX	See Note-1. Insufficient recent cost data.

Facility Unit Costs (UC) are average unit costs based on the most Recent 4-Year (2016-19) project awards per building type.
 All UC's are the average unit costs for new construction, escalated to 1 Oct 2022, using the Inflation Guidance for
 FY 2021 President's Budget, 3 April 2019 and Normalized to an Area Cost Factor of 1. Please refer to the "Notes" in the Remarks Column of Table.

CAT CODE	Description	Facility Average or Standard Size	Unit Of Measure (UoM)	FY22 Unit Cost (\$ / UoM)	Remarks
					Note-1: No data or Not enough useable Army Bid Data since 2016 to forecast UC. Note-2: Last year's unit cost (UC) escalated 1 year. Not enough projects awarded to forecast UC. Note-3: UC & Ref Size based on GUC / DOD / TriService Guidance.
14188	WT Unit Admin Fac, Large	XX	SF	XX	See Note-1. Insufficient recent cost data.
14188	WT Unit Admin Fac, Small	XX	SF	XX	See Note-1. Insufficient recent cost data.
14188	WT Company (CO) Admin Fac	XX	SF	XX	See Note-1. Insufficient recent cost data.
14184	WT Jt BN-CO Admin / Ops Fac	XX	SF	XX	See Note-1. Insufficient recent cost data.
72210	WT Dining Fac-Seating 251-500 Person	XX	SF	XX	See CATCD 72210, Dining Fac (DFAC), below for UC
74033	WT Soldiers and Family Assist. Ctr (SFSC)	XX	SF	XX	SFSC designs never launched.
74033	WT SFSC - Small	XX	SF	XX	SFSC designs never launched.
74033	WT SFSC - Large	XX	SF	XX	SFSC designs never launched.
Various	<u>OPERATIONAL READINESS TRAINING COMPLEX (ORTC)/ TRANSIENT TRAINING COMPLEX</u>				
	The ORTC Std design is based on a battalion sized ORTC to include Transient Barracks, Battalion HQ, Company HQ, Vehicle Maintenance, Dining, Officer Quarters, etc for transient trainees. These are more austere than permanent party facilities. No Cat Code exists for the Complex, utilize the catcode for the largest facility				
72114	ORTC Transient Training Barracks	51,738	SF	377.00	Ref size & UC based on project data in HII Published w/2 Louisville COS approved data points.
72412	Sn. Enlisted Officers Qtrs, Transient	XX	SF	XX	See Note-1. Insufficient recent cost data.
14184	Battalion HQ Bldg, Transient Trng	XX	SF	XX	See Note-1. Insufficient recent cost data.
14186	COF / Company HQ, Transient Trng	XX	SF	XX	See Note-1. Insufficient recent cost data.
14187	Brigade HQ Bldg, Transient Trng	XX	SF	XX	See Note-1. Insufficient recent cost data.
14179	Hardstand Cover (Canopy) - Transient Trng	XX	SF	XX	See CC 14179 under COF Complex above; incl Canopy column cost, no Hardstand cost
21406	Vehicle Maint Shop, Transient Trng	XX	SF	XX	See CC 21409 under the Army Reserve Organizational Maint Shop
72212	Dining Fac, 720 PN, Transient Trng	XX	SF	XX	See CC 72212 under Dining Facilities below
72212	Dining Fac, 1428 PN, Transient Trng	XX	SF	XX	See CC 72212 under Dining Facilities below
44222	Covered Storage Sheds	2,250	SF	See TEMF	See CC 44222, Storage Shed, under TEMF Complex above.
	<u>ADVANCE INDIVIDUAL TRAINING (AIT) COMPLEX</u>				
	A Standard AIT Barracks Complex consists of Brigade HQ, Battalion HQ, Barracks/COF Buildings for upto 4-300 person companies per BN, Dining Facility, and other required buildings and site facilities.				
72121	AIT Barracks w/CO Ops (COF) Space	183,700	SF	305.00	Note-2: Last year's unit cost (UC) escalated 1 year. Not enough projects awarded to forecast UC.
72121	AIT Barracks w/COF Space - Army Reserve	XX	SF	XX	See Note-1. Insufficient recent cost data.
14182	AIT Brigade HQS, if needed	9,100	SF	XX	See CC 14182, Brigade HQ provided earlier
14183	AIT Battalion HQS w/ Classrooms	12,300	SF	XX	See CC 14183, Battalion HQ provided earlier
72210	Dining Fac, AIT, 1300 PN, 544 seats	32,000	SF	424.00	Note-2: Last year's unit cost (UC) escalated 1 year. Not enough projects awarded to forecast UC. See 72210, SM Basic and AIT below
72210	Dining Fac, AIT, 2600 BN, 1088 seats	XX	SF	XX	See CC 72210, Large Basic and AIT Complex under DFAC below.
	<u>BASIC TRAINING (BT/IET) and ONE STATION UNIT TRAINING (OUST) BARRACKS COMPLEX</u>				
	A Standard BT/OUST Complex includes up to 5 - 64,700 SF each Barracks/Company Ops Bldgs for 1,200 soldiers, a Battalion HQ Bld/ classroom, a Dining Facility, and Lawn equipment Storage (2,000 SF) building, a 1/4 mile 8-lane running track and training pits.				
72181	BT/OUST Brks w/COF Space	267,875	SF	233.00	Ref size & UC based on project data in HII Published w/ 1 Ft. Worth COS approved data point.
	Calculate average individual Barrack/COF Bldg size, then use Size Adj. Factor Table-1, Part-I Table to determine BT Barracks/COF Bld UC using PAX Unit Cost.				
	BT/OUST Barracks Complex may contain 1, 2, 3, 4 or 5 Brks/COF Bldgs. Scope of Covered Training Area under Barracks w/CO Ops Space is included in each Bldg GSF				
72181	Battalion (BN) HQS w/Classrooms	XX	SF	XX	See Note-1. Insufficient recent cost data.
72210	Dining Fac for 1 BN, 1300 (PN) trainees, 544 seats	32,000	SF	XX	See CC 72210, Small Basic and AIT Dining under DFAC below
72210	Dining Fac for 2 BN, 2600 (PN) trainees, 1088 seats	55,000	SF	XX	Use Size Adj Table using 1300 trainee UC above for this facility
	Covered Queuing Area is included in the Dining Facility area calculation. Standard Reference Size for the BT/OUST Training Dining Facility is 30,500 SF.				
	<u>DINING FACILITIES (DFAC)</u>				

Facility Unit Costs (UC) are average unit costs based on the most Recent 4-Year (2016-19) project awards per building type. All UC's are the average unit costs for new construction, escalated to 1 Oct 2022, using the Inflation Guidance for FY 2021 President's Budget, 3 April 2019 and Normalized to an Area Cost Factor of 1. Please refer to the "Notes" in the Remarks Column of Table.					
CAT CODE	Description	Facility Average or Standard Size	Unit Of Measure (UoM)	FY22 Unit Cost (\$ / UoM)	Remarks
	Cost includes MCA Funded Kitchen equipment & installation. DFACs are categorized and, then unit cost for each size is developed separately.				
72210	DFAC - Permanent Party - Small, 400 - 600 PN, <15,000 SF	XX	SF	XX	See Note-1. Insufficient recent cost data.
72210	DFAC - Permanent Party - Medium, 1057-1716 PN, 15,000 to 39,999 SF	26,000	SF	610.00	See Note-3: UC & Ref Size based on GUC / DOD Guidance.
72210	DFAC - Permanent Party - Large, 1057-1716 PN, >40,000 SF	XX	SF	XX	See Note-1. Insufficient recent cost data.
72210	DFAC - Basic & AIT Complex - Small, 1300 PN, 544 Seats	32,000	SF	424.00	Note-2: Last year's unit cost (UC) escalated 1 year. Not enough projects awarded to forecast UC.
72210	DFAC - Basic & AIT Complex - Large, 2600 PN, 1088 seats	XX	SF	XX	See Note-1. Insufficient recent cost data.
72212	DFAC - ORTC - Small, 720 PN	XX	SF	XX	See Note-1. Insufficient recent cost data.
72212	DFAC - ORTC - Large, 1428 PN	21,300	SF	566.00	Note-2: Last year's unit cost (UC) escalated 1 year. Not enough projects awarded to forecast UC.
72410	Unaccompanied Officers Quarters	XX	SF	XX	See Note-1. Insufficient recent cost data.
72412	Transient Training Officers Quarters	XX	SF	XX	See CC 72412 Sn. Enlisted Officers Qtrs, Transient under ORTC.
73010	STAND ALONE FIRE STATIONS (FS) - FS & Air Rescue Fire Fighting Fire Stations (ARFF)				
	These are stand alone Fire Stations. Their sizes are determined by the authorized number of Apparatus Bays which house Vehicles, number of Dorm Emergency rooms, and whether they are HQs or Satellite Stations. A standard Apparatus Bay shall be 62' x 91' for a 2- or 3-CO Station; for a Air Rescue Fire Fighting (ARFF) is 70' x 91'				
73010	Airfield Fire/Crash Rescue Station	17,284	SF	361.00	Ref size & UC based on project data in HII Published w/ 1 Huntsville COS approved data point.
	CONSOLIDATED FIRE, SAFETY & SECURITY Facilities (FSS)/DEPT of EMERGENCY SERVICES (DES) Facilities				
	Combined Military Police, Safety, Fire & Emergency Svc. Also called Directorate of Emergency Services (DES) Facility				
73010	Consolidated FSS Fac - Medium	46,257	SF	404.00	Ref size & UC based on project data in HII Published w/ 1 Huntsville COS approved data point.
73016	Police/Law Enforcement (MP) Station	XX	SF	XX	See Note-1. Insufficient recent cost data.
73017	Chapel - includes Pew seating.	XX	SF	XX	See Note-1. Insufficient recent cost data.
73017	Chapel for Initial Entry Trainees (IET)	XX	SF	XX	See Note-1. Insufficient recent cost data.
73018	Religious Education Facility - Medium	XX	SF	XX	See Note-1. Insufficient recent cost data.
	For upto 10 small groups of 55-70 PN. A dedicated space for Religious Education and Religious Activities. Should be reported separately from the worship space if collocated in a Chapel, catcode 73017. Use Size Adjustment Factor Table-1, for other UC of other sizes.				
73019	Chapel Family Life Ctr (300-450 PN)	XX	SF	XX	See Note-1. Insufficient recent cost data.
	DEPENDENT SCHOOLS				
73046	Elementary School - CONUS	120,000	SF	310.00	See Note-3: UC & Ref Size based on GUC / DOD Guidance.
73046	Elementary School - OCONUS	120,000	SF	310.00	See Note-3: UC & Ref Size based on GUC / DOD Guidance.
73046	Elementary School - OCONUS, Other Than Japan locations	XX	SF	XX	See Note-1. Insufficient recent cost data.
73046	Junior High School	XX	SF	XX	See Note-1. Insufficient recent cost data.
73046	High School	XX	SF	XX	See Note-1. Insufficient recent cost data.
74010	Auditorium, General Purpose	XX	SF	XX	See Note-1. Insufficient recent cost data.
74011	Bowling Center	XX	SF	XX	See Note-1. Insufficient recent cost data.
74012	Cafeteria	XX	SF	XX	See Note-1. Insufficient recent cost data.
74016	CDC - School Age, >6 years of age	XX	SF	XX	See Note-1. Insufficient recent cost data.
74017	CDC - Preschool, 232 children, 0-6 yrs	XX	SF	XX	See Note-1. Insufficient recent cost data.
74021	Commissary	XX	SF	XX	See Note-1. Insufficient recent cost data.
74022	Skill Development Center	XX	SF	XX	See Note-1. Insufficient recent cost data.
74023	Credit Union	XX	SF	XX	See Note-1. Insufficient recent cost data.
74024	Skill Development Ctr - Automotive	XX	SF	XX	See Note-1. Insufficient recent cost data.
74025	Education Center for 10,000 - 15,000 PN	XX	SF	XX	See Note-1. Insufficient recent cost data.

Facility Unit Costs (UC) are average unit costs based on the most Recent 4-Year (2016-19) project awards per building type.

All UC's are the average unit costs for new construction, escalated to 1 Oct 2022, using the Inflation Guidance for

FY 2021 President's Budget, 3 April 2019 and Normalized to an Area Cost Factor of 1. Please refer to the "Notes" in the Remarks Column of Table.

CAT CODE	Description	Facility Average or Standard Size	Unit Of Measure (UoM)	FY22 Unit Cost (\$ / UoM)	Remarks
					Note-1: No data or Not enough useable Army Bid Data since 2016 to forecast UC. Note-2: Last year's unit cost (UC) escalated 1 year. Not enough projects awarded to forecast UC. Note-3: UC & Ref Size based on GUC / DOD / TriService Guidance.
74028	Physical Fitness Facility	XX	SF	XX	See Note-1. Insufficient recent cost data.
	Program Indoor Swimming Pool (CC74042) separately				
74030	Sports Pro Shop	XX	SF	XX	See Note-1. Insufficient recent cost data.
74033	Army Community Service	XX	SF	XX	See Note-1. Insufficient recent cost data.
74041	Main Library	XX	SF	XX	See Note-1. Insufficient recent cost data.
74047	Service Club	XX	SF	XX	See Note-1. Insufficient recent cost data.
74048	Officer Open Dining Facility	XX	SF	XX	See Note-1. Insufficient recent cost data.
74053	Main Exchange	XX	SF	XX	See Note-1. Insufficient recent cost data.
74056	Exchange Service Outlet	XX	SF	XX	See Note-1. Insufficient recent cost data.
74066	Youth Center, medium (105-135 PN)	XX	SF	XX	See Note-1. Insufficient recent cost data.
74068	Recreation Center	XX	SF	XX	See Note-1. Insufficient recent cost data.
74070	Indoor Roller Skating Rink	XX	SF	XX	See Note-1. Insufficient recent cost data.
74072	25 meter Indoor Swimming Pool	XX	SF	XX	See Note-1. Insufficient recent cost data.
74075	Recreational Support Building	XX	SF	XX	See Note-1. Insufficient recent cost data.
	PLAYGROUND for PPRESCHOOL CHILDREN, UNDER 6 YEARS of AGE				
75018	Small (126 children)	XX	SF	XX	See Note-1. Insufficient recent cost data.
75018	Medium (232 Children)	XX	SF	XX	See Note-1. Insufficient recent cost data.
75018	Large (338 Children)	XX	SF	XX	See Note-1. Insufficient recent cost data.
	PLAYGROUND for SCHOOL AGE CHILDREN, 6 TO 10 YEARS				
75018	Small (105-135 children)	XX	SF	XX	See Note-1. Insufficient recent cost data.
75018	Medium/Large (150-225 Children)	XX	SF	XX	See Note-1. Insufficient recent cost data.
75018	Play Ground for Youth Center	XX	SF	XX	See Note-1. Insufficient recent cost data.
75022	Multipurpose Athletics Field (360' x 160')	XX	EA	XX	See Note-1. Insufficient recent cost data.
75027	Running Track	XX	EA	XX	See Note-1. Insufficient recent cost data.
75030	Outdoor Swimming Pool	XX	SF	XX	See Note-1. Insufficient recent cost data.
75061	Bleacher, Covered	XX	EA	XX	See CC 75061 under Range Complex above for UC
85210	Organizational Vehicle Parking	XX	SY	XX	See Note-1. Insufficient recent cost data.
85218	Parking Garage, Multistoried	110,000	SF	55.00	See Note-3: UC & Ref Size based on GUC / DOD Guidance.
	Assumes 425-450 SF/vehicle with turning radii and ramps.				
89120	Plant / Utilities Building	XX	SF	XX	See Note-1. Insufficient recent cost data.
	SPECIAL FOUNDATIONS				
	Piling, Treated Wood, 50' long, 12" butt	N/A	SF	43.00	See Note-2. Used FY17 PAX 3.2.2 UC escalated to 1 Oct 2019 for FY20 Projects
	Piling, Concrete, 14" square	N/A	SF	64.00	See Note-2. Used FY17 PAX 3.2.2 UC escalated to 1 Oct 2019 for FY20 Projects
	Piling, Concrete, 16" square	N/A	SF	66.00	See Note-2. Used FY17 PAX 3.2.2 UC escalated to 1 Oct 2019 for FY20 Projects
	Piling, Concrete, 18" diameter	N/A	SF	75.00	See Note-2. Used FY17 PAX 3.2.2 UC escalated to 1 Oct 2019 for FY20 Projects
	Piling, Steel H, 50' Long, HP 12x53	N/A	SF	52.00	See Note-2. Used FY17 PAX 3.2.2 UC escalated to 1 Oct 2019 for FY20 Projects
	Piling, Steel Pipe, 12" D, Conc. Filled	N/A	SF	63.00	See Note-2. Used FY17 PAX 3.2.2 UC escalated to 1 Oct 2019 for FY20 Projects
Legend:	Note-1: No data available or not enough usable award data since FY2016 to forecast UC				
	Note-2: Not enough usable award data since FY2016 to forecast UC. Last year's PAX UC escalated with new inflation rate.				
	Note-3: UC & reference size based on GUC / DOD guidance.				

APPENDIX A - SUPPORT FACILITIES UNIT COST TABLE (PART - II, Support Facilities).

NOTE: The Support Fac Unit Costs are for guidance only. Adjustment to these Unit Costs are allowed when local cost data are available with back-ups.

<u>CAT CODE</u>	<u>ITEM</u>	<u>QTY</u>	<u>UNIT</u>	<u>UNIT COST (\$/UNIT)</u>
	<u>AIRFIELD RUNWAY (RW)</u> - SLIP FORM CONC PVMT, Airports, UNREINFORCED, 5000 PSI, 12' PASS, Incl JOINTS, FINISHING & CURING			
11110 & X20	8" THICK (TH) PAVEMENT	1	SY	\$45.20
	10" THICK PAVEMENT	1	SY	\$54.00
	12" THICK PAVEMENT	1	SY	\$61.00
	16" THICK PAVEMENT	1	SY	\$82.00
	<u>AIRFIELD RUNWAY</u> - FIXED FORM PLAIN CEMENT CONC PVMT, Airports, UNREINFORCED, 4500 PSI, 12' PASS, INCLUDES JOINT, FINISHING, & CURING			
11110 & X20	12 " THICK PAVEMENT, Note: ADD \$14.45/SY For REINF STEEL BAR, 18 LBS/SY (A185)	1	SY	\$61.00
	14" THICK PAVEMENT, Note: ADD \$14.45 /SY For REINF STEEL BAR, 18 LBS/SY (A185)	1	SY	\$73.00
	16" THICK PAVEMENT, Note: ADD \$14.45/SY For REINF STEEL BAR, 18 LBS/SY (A185)	1	SY	\$82.00
	<u>ASHPHALT PAVING</u> - PLANT MIX For HIGHWAYS & LARGE PAVED AREAS, WEARING COURSE			
11110 & X20	3" THICK PVMT	1	SY	\$18.90
	<u>AIRFIELD RUNWAY</u> - LIGHTING, BI-DIRECTIONAL W/ SHALLOW INSERT BASE			
11110 & X20	RW CENTER LINE LIGHT, SEMI FLUSH, 200 W	1	EA	\$2,419.00
	RW CENTER LINE LIGHT, FLUSH, 200 W	1	EA	\$2,419.00
	RW EDGE & THRESHOLD LIGHT, 200 W, BI-DIRECTIONAL for Base Housing	1	EA	\$1,603.00
	RW EDGE & THRESHOLD LIGHT, 2-115 W, Bi-DIRECTIONAL for Base Housing	1	EA	\$2,138.00
	TOUCHDOWN ZONE LIGHT, 200 W, UNIDIRECTIONAL for Base Housing	1	EA	\$2,052.00
	THRESHOLD & APPROACH LIGHT, 200 W, UNIDIRECTIONAL for Base Housing	1	EA	\$1,019.00
	<u>AIRFIELD PVMT MARKINGS</u>			
11110	THERMOPLASTIC PVMT MARKINGS, RUNWAY w/24 LB GLASS BEADS Per 100 SF	1	SF	\$4.40
	PVMT MARKINGS, TAXIWAY, PAINTING WHITE OR YELLOW STRIPES	1	SF	\$1.30
	<u>COMMUNICATIONS (COMM) DISTRIBUTION CABLE, CABLE SPLICING & TERMINATION</u> - UNDERGROUND RESIDENTIAL DISTRIBUTION (URD) or SIMILAR			
13510	CABLE SPLICING, 5 kV, #6 STRANDED to #1 STRANDED, URD or SIMILAR	1	EA	\$355.00
	CABLE SPLICING, 15 kV, #6 STRANDED to #1 STRANDED, URD or SIMILAR	1	EA	\$427.00

APPENDIX A - SUPPORT FACILITIES UNIT COST TABLE (PART - II, Support Facilities).

NOTE: The Support Fac Unit Costs are for guidance only. Adjustment to these Unit Costs are allowed when local cost data are available with back-ups.

<u>CAT CODE</u>	<u>ITEM</u>	<u>QTY</u>	<u>UNIT</u>	<u>UNIT COST (\$/UNIT)</u>
	CABLE SPLICING, 25 kV, #6 STRANDED to #1 STRANDED, URD or SIMILAR	1	EA	\$461.00
13510	CABLE SPLICING, 5 kV, #1 STRANDED to #4/0 STRANDED, URD or SIMILAR	1	EA	\$394.00
	CABLE SPLICING, 15 kV, #1 STRANDED to #4/0 STRANDED, URD or SIMILAR	1	EA	\$478.00
	CABLE SPLICING, 25 kV, #1 STRANDED to #4/0 STRANDED, URD or SIMILAR	1	EA	\$487.00
13510	CABLE SPLICING, 5 kV, #4/0 STRANDED to 500 kcmil STRANDED, URD or SIMILAR	1	EA	\$416.00
	CABLE SPLICING, 15 kV, #4/0 STRANDED to 500 kcmil STRANDED, URD or SIMILAR	1	EA	\$473.00
	CABLE SPLICING, 25 kV, #4/0 STRANDED to 500 kcmil STRANDED, URD or SIMILAR	1	EA	\$697.00
13510	CABLE SPLICING, 5 kV, 500 kcmil STRANDED, URD or SIMILAR	1	EA	\$534.00
	CABLE SPLICING, 15 kV, 500 kcmil STRANDED, URD or SIMILAR	1	EA	\$670.00
	CABLE SPLICING, 25 kV, 500 lcmil STRANDED, URD or SIMILAR	1	EA	\$731.00
	CABLE SPLICING, 5 kV, 600 kcmil STRANDED, URD or SIMILAR	1	EA	\$557.00
	CABLE SPLICING, 15 kV, 600 kcmil STRANDED, URD or SIMILAR	1	EA	\$720.00
	CABLE SPLICING, 25 kV, 600 kcmil STRANDED, URD or SIMILAR	1	EA	\$782.00
13510	CABLE SPLICING, 5 kV, 750 kcmil STRANDED, URD or SIMILAR	1	EA	\$591.00
	CABLE SPLICING, 15 kV, 750 kcmil STRANDED, URD or SIMILAR	1	EA	\$748.00
	CABLE SPLICING, 25 kV, 750 kcmil STRANDED, URD or SIMILAR	1	EA	\$799.00
	CABLE SPLICING, 5 kV, 1000 kcmil STRANDED, URD or SIMILAR	1	EA	\$629.00
	CABLE SPLICING, 15 kV, 1000 kcmil STRANDED, URD or SIMILAR	1	EA	\$832.00
	CABLE SPLICING, 25 kV, 1000 kcmil STRANDED, URD or SIMILAR	1	EA	\$996.00
	<u>TERMINALE LUGS, SOLDERLESS</u>			
13510	TERMINAL LUGS, #16 to #10, SOLDERLESS	1	EA	\$16.60
	TERMINAL LUGS, #8 to #4, SOLDERLESS	1	EA	\$28.80
	TERMINAL LUGS, #2 to #1, SOLDERLESS	1	EA	\$37.10

APPENDIX A - SUPPORT FACILITIES UNIT COST TABLE (PART - II, Support Facilities).

NOTE: The Support Fac Unit Costs are for guidance only. Adjustment to these Unit Costs are allowed when local cost data are available with back-ups.

<u>CAT CODE</u>	<u>ITEM</u>	<u>QTY</u>	<u>UNIT</u>	<u>UNIT COST (\$/UNIT)</u>
13510	TERMINAL LUGS, 1/0 to 2/0, SOLDERLESS	1	EA	\$52.00
	TERMINAL LUGS, 3/0, SOLDERLESS	1	EA	\$68.00
	TERMINAL LUGS, 4/0, SOLDERLESS	1	EA	\$74.00
	TERMINAL LUGS, 250 kcmil, SOLDERLESS	1	EA	\$92.00
	TERMINAL LUGS, 500 kcmil, SOLDERLESS	1	EA	\$142.00
	TERMINAL LUGS, 750 kcmil, SOLDERLESS	1	EA	\$165.00
	<u>FIBER OPTIC CABLE, SPLICER BOX & TERMINATION BOX</u>			
13510	12 STRAND FIBER OPTIC CABLE w/ 1" PVC INNER DUCT RUN IN DUCTBANK	1	LF	\$2.30
	24 STRAND FIBER OPTIC CABLE w/ 1" PVC INNER DUCT RUN IN DUCTBANK	1	LF	\$2.80
	36 STRAND FIBER OPTIC CABLE w/ 1" PVC INNER DUCT RUN IN DUCTBANK	1	LF	\$3.10
	6 STRAND FIBER OPTIC SPLICE BOX, INCL BOX & 6 CABLE SPLICES	1	EA	\$471.00
	12 STRAND FIBER OPTIC SPLICE BOX, INCL BOX & 12 CABLE SPLICES	1	EA	\$568.00
	24 STRAND FIBER OPTIC SPLICE BOX, INCL BOX & 24 CABLE SPLICES	1	EA	\$769.00
	36 STRAND FIBER OPTIC SPLICE BOX, INCL BOX & 36 CABLE SPLICES	1	EA	\$976.00
	6 STRAND FIBER OPTIC TERMINATION BOX, INCL BOX & 6 CABLE CONNECTIONS	1	EA	\$603.00
	12 STRAND FIBER OPTIC TERMINATION BOX, INCL BOX & 12 CABLE CONNECTIONS	1	EA	\$689.00
	24 STRAND FIBER OPTIC TERMINATION BOX, INCL BOX W/ 2 SPLICE TRAYS & 24 CABLE CONNECTIONS	1	EA	\$924.00
	36 STRAND FIBER OPTIC TERMINATION BOX, INCL BOX & w/ 3 SPLICE TRAYS & 36 CABLE CONNECTIONS	1	EA	\$1,148.00
81160	<u>STANDBY GENERATOR, DIESEL (SDG) , 3 PHASE 4 WIRE, 277/480 VOLTS,</u> INCL. BATTERY, CHARGER, FUEL TANK, MUFFLER & AUTO TXFR SWITCH (ATS), EXCL. CONDUIT, WIRING & CONC PAD	75 kW	EA	\$83,990.00
		125 kW	EA	\$98,690.00
		200 kW	EA	\$128,490.00
		300 kW	EA	\$157,480.00
		400 kW	EA	\$213,480.00
		500 kW	EA	\$264,790.00
		750 kW	EA	\$411,770.00

APPENDIX A - SUPPORT FACILITIES UNIT COST TABLE (PART - II, Support Facilities).

NOTE: The Support Fac Unit Costs are for guidance only. Adjustment to these Unit Costs are allowed when local cost data are available with back-ups.

<u>CAT CODE</u>	<u>ITEM</u>	<u>QTY</u>	<u>UNIT</u>	<u>UNIT COST (\$/UNIT)</u>
		1000 kW	EA	\$517,920.00
	<u>SITE LIGHTING, UNDERGROUND DISTRIBUTION</u> , EXCL. POLES & LIGHT FIXTURE COSTS			
81230	1" PVC CONDUIT, # 10- 3 STRAND COPPER WIRE, 150 LF DIRECT BURIAL, INCL EXCAVATION & BACKFILL	150	LF	\$2,419.00
	<u>SITE LIGHTING W/ LIGHT POLE & LIGHT FIXTURE ASSEMBLY</u> , EXCL UNDERGROUND DISTRIBUTION, WIRING, EXCAVATION & BACKFILL			
81230	20' ALUMINUM POLE, 400 WATT HIGH PRESSURE SODIUM (HPS)	1	EA	\$3,881.00
	40' ALUMINUM POLE, 1000 WATT HIGH PRESSURE SODIUM (HPS)	1	EA	\$6,750.00
	40' HIGH FIBERGLASS POLE, 1000 WATT HIGH PRESSURE SODIUM (HPS)	1	EA	\$5,541.00
	20' ALUMINUM POLE, 400 WATT METAL HALIDE (MH)	1	EA	\$3,825.00
	40' ALUMINUM POLE, 1000 WATT METAL HALIDE (MH)	1	EA	\$6,694.00
	40' HIGH FIBERGLASS POLE, 1000 WATT METAL HALIDE (MH)	1	EA	\$5,457.00
	<u>OVERHEAD (OH) ELECTRIC LINES</u> - INCL. COST OF WOOD POLES @ 250' SPACING, 3 PHASE 4 Wire ALUMINUM CONDUCTOR STEEL REINF			
81241	H-FRAME DISTRIBUTION LINES, 15-69 kV SHORT LINES w/ CROSS ARM & INSUL	1,000	LF	\$50,400.00
	OVERHEAD LINES BELOW 15 kV w/ CROSS ARMS & INSULATORS	1,000	LF	\$47,370.00
	<u>U/G ELECTRIC LINES (DIRECT BURIAL (DB))</u> - INCL. Cost of COPPER Service Entrance CABLE (SEU) CONDUCTOR, CHAIN EXCAVATOR to 3" and BACKFILL			
81242	# 1/0 -3/C, 600 Volt DB, SEU COPPER CONDUCTOR, EXCAV & BACKFILL	1	LF	\$478.00
	# 4/0 - 3/C, 600 Volt DB, SEU COPPER CONDUCTOR, EXCAV & BACKFILL	1	LF	\$578.00
	<u>CABLE TERMINATORS</u> - OUT DOOR SYSTEMS			
81242	CABLE TERMINATION, 15 kV, #1 SOLID to 4/0 STRANDED	1	EA	\$389.00
	CABLE TERMINATION, 15 kV, #2/0 SOLID to 350 KCMIL STRANDED	1	EA	\$422.00
	CABLE TERMINATION, 15 kV, 400 KCMIL to 750 KCMIL STRANDED	1	EA	\$483.00
	<u>CABLE SPLICING</u> , 15 kV, UNDERGROUND RESIDENTIAL DISTRIBUTION (URD) CABLE or SIMILAR			
81242	CABLE SPLICING, URD or SIMILAR, #1 STRANDED to 4/0 STRANDED,	1	EA	\$478.00
	CABLE SPLICING, URD or SIMILAR, 4/0 STRANDED to 500 KCMIL STRANDED	1	EA	\$578.00

APPENDIX A - SUPPORT FACILITIES UNIT COST TABLE (PART - II, Support Facilities).

NOTE: The Support Fac Unit Costs are for guidance only. Adjustment to these Unit Costs are allowed when local cost data are available with back-ups.

<u>CAT CODE</u>	<u>ITEM</u>	<u>QTY</u>	<u>UNIT</u>	<u>UNIT COST (\$/UNIT)</u>
	<u>UNDERGROUND (UGND) ELECTRIC DUCTBANKS</u> - INCL Cost of EXCAVATION (EXCAV), CAST IN PLACE (CIP) CONC & BACKFILL to 3' DEEP			
81242	1-WAY-4" Diameter (DIA) PVC, ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$20.50
	2-WAY-4" DIA PVC, ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$36.00
	4-WAY-4" DIA PVC, ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$62.00
	6-WAY-6" DIA PVC, ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$145.00
81242	1-WAY-2" DIA RIGID GALVANIZED STEEL (RGS) ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$28.80
	1-WAY-3" DIA RGS, ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$52.00
	1-WAY-4" DIA RGS, ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$65.00
	1-WAY-5" DIA RGS, ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$91.00
	1-WAY-6" DIA RGS, ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$113.00
81242	2-WAY-2" DIA RGS, ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$43.20
	2 WAY-3" DIA RGS, ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$74.00
	2-WAY-4" DIA RGS, ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$102.00
	2-WAY-5" DIA RGS, ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$167.00
	2-WAY-6" DIA RGS, ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$235.00
81242	3-WAY-2" DIA RGS, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$63.00
	3-WAY-3" DIA RGS, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$105.00
	3-WAY-4" DIA RGS, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$145.00
	3-WAY-5" DIA RGS, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$241.00
	3-WAY-6" DIA RGS, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$338.00
81242	4-WAY-2" DIA RGS, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$83.00
	4-WAY-3" DIA RGS, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$135.00
	4-WAY-4" DIA RGS, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$189.00
	4-WAY-5" DIA RGS, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$314.00
	4-WAY-6" DIA RGS, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$445.00

APPENDIX A - SUPPORT FACILITIES UNIT COST TABLE (PART - II, Support Facilities).

NOTE: The Support Fac Unit Costs are for guidance only. Adjustment to these Unit Costs are allowed when local cost data are available with back-ups.

<u>CAT CODE</u>	<u>ITEM</u>	<u>QTY</u>	<u>UNIT</u>	<u>UNIT COST (\$/UNIT)</u>
81242	1-WAY-2" DIA PVC, ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$17.30
	1-WAY-3" DIA PVC, ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$20.20
	1-WAY-4" DIA PVC, ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$24.30
	1-WAY-5" DIA PVC, ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$28.20
	1-WAY-6" DIA PVC, ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$33.80
81242	2-WAY-2" DIA PVC, ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$26.90
	2-WAY-3" DIA PVC, ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$32.00
	2-WAY-4" DIA PVC, ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$38.90
	2-WAY-5" DIA PVC, ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$46.70
	2-WAY-6" DIA PVC, ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$58.00
81242	4-WAY-2" DIA PVC, ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$42.20
	4-WAY-3" DIA PVC, ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$51.00
	4-WAY-4" DIA PVC, ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$61.00
	4-WAY-5" DIA PVC, ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$73.00
	4-WAY-6" DIA PVC, ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$95.00
81242	6-WAY-4" DIA PVC, ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$94.00
	6-WAY-5" DIA PVC, ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$111.00
	6-WAY-6" DIA PVC, ENCASED BURIAL, INCL EXCAV, CIP CONC & BACKFILL	1	LF	\$150.00
	<u>ELECTRICAL (ELECT) UNDERGROUND (UGND) MANHOLES (MH)</u>, EXCL COST OF EXCAVATION, CIP CONC & BACKFILL			
81242	UGND HAND HOLES, 4' x 4' x 4' DEEP, PRECAST CONC w/ COVER, EXCL EXCAV, CIP CONC & BACKFILL	1	EA	\$3,094.00
	ELECT UGND MH, 6' x 10' x 7' DEEP, PRECAST w/ IRON RACKS & PULLING IRONS, C.I. FRAME & COVER	1	EA	\$13,050.00
	ELECT UGND MH, 6' x 8' x 7' DEEP, PRECAST w/ IRON RACKS & PULLING IRONS, C.I. FRAME & COVER	1	EA	\$11,710.00
81320	<u>SUBSTATION, LOAD INTERRUPTER SWITCH, 600 AMP</u> , 2 POSITION, 3 KVA & BELOW W/ CLF FUSES, 4.8 KV, 6000 AMP, NEMA 1 & GROUNDING LOOP	1	EA	\$34,200.00

APPENDIX A - SUPPORT FACILITIES UNIT COST TABLE (PART - II, Support Facilities).

NOTE: The Support Fac Unit Costs are for guidance only. Adjustment to these Unit Costs are allowed when local cost data are available with back-ups.

<u>CAT CODE</u>	<u>ITEM</u>	<u>QTY</u>	<u>UNIT</u>	<u>UNIT COST (\$/UNIT)</u>
	<u>TRANSFORMERS (XFMR)</u> - INCL COST of PAD MOUNTING w/ BOLLARDS AND GROUNDING LOOP			
81360	XFMR 150 kVA, OIL FILLED, 5 kV or 15 kV w/ TAPS, 277/480 V SECONDARY 3 PHASE	1	EA	\$21,490.00
	XFMR 225 kVA, OIL FILLED, 15 kV w/TAPS, 480 V SECONDARY 3 PHASE	1	EA	\$23,740.00
	XFMR 500 kVA, OIL FILLED, 15 kV W/ TAPS, 480 V SECONDARY 3 PHASE	1	EA	\$28,010.00
	XFMR 1,000 kVA, OIL FILLED, 15 kV W/ TAPS, 480 V SECONDARY 3 PHASE	1	EA	\$50,860.00
	XFMR 2,000 KVA, OILL FILLED, 15 kV W/ TAPS, 480 V SECONDARY 3 PHASE	1	EA	\$71,430.00
81360	XFMR 15 kVA, DRY TYPE, SINGLE PHASE, 240/480 V PRIMARY 120/240 V SECONDARY	1	EA	\$9,450.00
	XFMR 25 kVA, DRY TYPE, SINGLE PHASE, 240/480 V PRIMARY 120/240 V SECONDARY	1	EA	\$10,430.00
	XFMR 37.5 kVA, DRY TYPE, SINGLE PHASE, 240/480 V PRIMARY 120/240 V SECONDARY	1	EA	\$11,590.00
	XFMR 50 kVA, DRY TYPE, SINGLE PHASE, 240/480 V PRIMARY 120/240 V SECONDARY	1	EA	\$12,600.00
	XFMR 75 kVA, DRY TYPE, SINGLE PHASE, 240/480 V PRIMARY 120/240 V SECONDARY	1	EA	\$14,070.00
	XFMR 100 kVA, DRY TYPE, SINGLE PHASE, 240/480 V PRIMARY 120/240 V SECONDARY	1	EA	\$15,750.00
	XFMR 167 kVA, DRY TYPE, SINGLE PHASE, 240/480 V PRIMARY 120/240 V SECONDARY	1	EA	\$20,700.00
81360	XFMR, 75 kVA, DRY TYPE - VENTILATED, 3 PHASE 480 V PRIMARY 120/208 V SECONDARY	1	EA	\$11,250.00
	XFMR, 112.5 kVA, DRY TYPE - VENTILATED, 3 PHASE 480 V PRIMARY 120/208 V SECONDARY	1	EA	\$12,370.00
	XFMR, 150 kVA, DRY TYPE - VENTILATED, 3 PHASE 480 V PRIMARY 120/208 V SECONDARY	1	EA	\$13,610.00
	XFMR, 225 kVA, DRY TYPE - VENTILATED, 3 PHASE 480 V PRIMARY 120/208 V SECONDARY	1	EA	\$16,200.00
	XFMR, 500 kVA, DRY TYPE - VENTILATED, 3 PHASE 480 V PRIMARY 120/208 V SECONDARY	1	EA	\$25,100.00
	XFMR, 750 kVA, DRY TYPE - VENTILATED, 3 PHASE 480 V PRIMARY 120/208 V SECONDARY	1	EA	\$37,130.00
	XFMR, 1000 kVA, DRY TYPE - VENTILATED, 3 PHASE 480 V PRIMARY 120/208 V SECONDARY	1	EA	\$41,400.00
81360	XFMR, 10 kVA, DRY TYPE On 36' POLE, 240/480 V PRIMARY 120/240 V SECONDARY	1	EA	\$5,034.00
	XFMR, 15 KVA, DRY TYPE On 36' POLE, 240/480 V PRIMARY 120/240 V SECONDARY	1	EA	\$5,625.00
	XFMR, 25 kVA, DRY TYPE On 36' POLE, 240/480 V PRIMARY 120/240 V SECONDARY	1	EA	\$6,610.00
81360	<u>MAIN POWER (PWR) TRANSFORMER (XFMR)</u> - INCL COST Of PAD MOUNTING (MTD) W/BOLLARDS & GROUNDING LOOP (GL)			

APPENDIX A - SUPPORT FACILITIES UNIT COST TABLE (PART - II, Support Facilities).

NOTE: The Support Fac Unit Costs are for guidance only. Adjustment to these Unit Costs are allowed when local cost data are available with back-ups.

<u>CAT CODE</u>	<u>ITEM</u>	<u>QTY</u>	<u>UNIT</u>	<u>UNIT COST (\$/UNIT)</u>
	MAIN PWR XFMR 46 kV, PAD MTD, w/ BOLLARDS & GL (1 MVA = 1,000 kVA)	1	KVA	\$38.00
	MAIN PWR XFMR 110 kV, PAD MTD, w/ BOLLARDS & GL (1 MVA = 1,000 kVA)	1	KVA	\$32.50
	MAIN PWR XFMR 161 kV, PAD MTD, W/ BOLLARDS & GL (1 MVA = 1,000 kVA)	1	KVA	\$30.40
	MAIN PWR XFMR 500 kV, PAD MTD, W/ BOLLARDS & GL (1 MVA = 1,000 kVA)	1	KVA	\$29.80
81360	<u>TRANSFORMERS (XFMR)</u> - INCL COST OF PAD MOUNTING (MTD) W/BOLLARDS AND GROUNDING LOOP (GL)			
	112.5 kVA XFMR, PAD MTD, 13,800 VOLTS TO 480/277 VOLTS W/ BOLLARDS & GL	1	EA	\$55,910.00
	150 kVA XFMR, PAD MTD, 13,800 VOLTS TO 480/277 VOLTS W/ BOLLARDS & GL	1	EA	\$56,820.00
	225 kVA XFMR, PAD MTD, 13,800 VOLTS TO 480/277 VOLTS W/ BOLLARD & GL	1	EA	\$64,690.00
	500 kVA XFMR, PAD MTD, , 13,800 VOLTS TO 480/277 VOLTS	1	EA	\$73,700.00
	<u>STEAM (ST) CONDENSATE LINES, UNDERGROUND (UGND)</u> - FROM CENTRAL PLANT TO BUILDING			
	<u>COMMON CONDUIT, UGND</u> - COMBINED STEAM (ST) SUPPLY & CONDENSATE (CNDS) RETURN (RTN) PIPES, INCL FITTINGS, TESTING & STEAM MANHOLES @ 250' O.C., 3' DEEP EXCAV & BACKFILL			
82210	2" ST & 1-1/4" CNDS RTN PIPE, PREFAB BLACK STEEL in 12-3/4" INSL CASE W/ MH @ 250' O.C.	1	LF	\$568.00
	1-1/2" ST & 1-1/2" CNDS RTN PIPE, PREFAB BLACK STEEL in 10-3/4" INSUL CASE W/ MH @ 250' O.C.	1	LF	\$563.00
	1-1/4" ST & 1-1/2" CNDS RTN PIPE, PREFAB BLACK STEEL in 10-3/4" INSUL CASE W/ MH @ 250' O.C.	1	LF	\$563.00
	1" ST & 1" CNDS RTN PIPE, PREFAB BLACK STEEL in 10-3/4" INSUL CASE W/ MH @ 250' O.C.	1	LF	\$563.00
	<u>SINGLE CONDUIT</u> - STEAM OR HIGH PRESSURE WATER PIPE, w/ INSULATED CASE ON SUPPORTS, INCL FITTINGS (FTG) & TESTING (TST)			
82210	1-1/4" ST PIPE, PREFAB BLACK STEEL in 12-3/4" INSUL CASE ON SUPPORTS, INCL FTG & TST	1	LF	\$350.00
	1-1/2" ST PIPE, PREFAB BLACK STEEL in 12-3/4" INSUL CASE ON SUPPORTS, INCL FTG & TST	1	LF	\$350.00
	2" ST PIPE, PREFAB BLACK STEEL in 12-3/4" INSUL CASE ON SUPPORTS, INCL FTG & TST	1	LF	\$365.00
	2-1/2" ST PIPE, PREFAB BLACK STEEL in 12-3/4" INSUL CASE ON SUPPORTS, INCL FTG & TST	1	LF	\$389.00
	3" ST PIPE, PREFAB BLACK STEEL in 14" INSUL CASE ON SUPPORTS, INCL FTG & TST	1	LF	\$389.00
	4" ST PIPE, PREFAB BLACK STEEL in 14" INSUL CASE ON SUPPORTS, INCL FTG & TST	1	LF	\$422.00
	6" ST PIPE, PREFAB BLACK STEEL in 18" INSUL CASE ON SUPPORTS, INCL FTG & TST	1	LF	\$522.00
	<u>CONCRETE TRENCH</u> W/ COVER for STEAM AND HOT WATER PIPING			

APPENDIX A - SUPPORT FACILITIES UNIT COST TABLE (PART - II, Support Facilities).

NOTE: The Support Fac Unit Costs are for guidance only. Adjustment to these Unit Costs are allowed when local cost data are available with back-ups.

<u>CAT CODE</u>	<u>ITEM</u>	<u>QTY</u>	<u>UNIT</u>	<u>UNIT COST (\$/UNIT)</u>
82210	18" DEEP x 24" WIDE x 6" THICK WALL w/ CONC COVER	1	LF	\$161.00
	<u>HOT WATER LINES, UNDERGROUND</u>			
82220	COMMON CONDUIT - COMBINED HOT WATER (HW) SUPPLY & RETURN (RTN) PIPES , PREFABRICATED BLACK STEEL, INSULATED CASE, INCL FITTINGS (FTG), TESTING TST), EXCAVATION & BACKFILL			
	1" HW & 1" RET PIPE in 10-3/4" PREFAB BLACK STEEL INSUL CASE, INCL EXCAV, BKFL, FTG & TST	1	LF	\$416.00
	1-1/2" HW & 1-1/2" RET PIPE in 10-3/4" PREFAB BLACK STEEL INSUL CASE, INCL EXCAV, BKFL, FTG & TST	1	LF	\$416.00
	2" HW & 2" RET PIPE in 10-3/4" PREFAB BLACK STEEL INSUL CASE, INCL EXCAV, BKFL, FTG & TST	1	LF	\$422.00
	3" HW & 3" RET PIPE in 16" PREFAB BLACK STEEL INSUL CASE, INCL EXCAV, BKFL, FTG & TST	1	LF	\$478.00
	4" HW & 4" RET PIPE in 10" PREFAB BLACK STEEL INSUL CASE, INCL EXCAV, BKFL, FTG & TST	1	LF	\$629.00
	<u>STEAM DISTRIBUTION MANHOLE (MH)</u> , PREFAB STEEL			
82220	STEAM DISTRIBUTION MANHOLE (MH) , PREFAB STEEL, 8' X 6' HT, INCL MH VENT, PIPING, CONDUIT & LADDER	1	EA	\$19,130.00
	<u>GAS PIPELINES</u> for PLAIN & NATURAL GAS PIPING (PNG) - PLAIN END, TAR COATED (CTD) & WRAPPED, INCL EXCAVATION & BACKFILL			
82410	1" DIA. STEEL PIPE, SCHEDULE 40, PLAIN END, TAR CTD, INCL EXCAV & BKFL	1	LF	\$25.30
	2" DIA. STEEL PIPE, SCHEDULE 40, PLAIN END, TAR CTD, INCL EXCAV & BKFL	1	LF	\$30.40
	3" DIA. STEEL PIPE, SCHEDULE 40, PLAIN END, TAR CTD, INCL EXCAV & BKFL	1	LF	\$38.90
	4" DIA. STEEL PIPE, SCHEDULE 40, PLAIN END, TAR CTD, INCL EXCAV & BKFL	1	LF	\$52.00
	6" DIA. STEEL PIPE, SCHEDULE 40, PLAIN END, TAR CTD, INCL EXCAV & BKFL	1	LF	\$80.00
	8" DIA. STEEL PIPE, SCHEDULE 40, PLAIN END, TAR CTD, INCL EXCAV & BKFL	1	LF	\$112.00
	12" DIA. STEEL PIPE, SCHEDULE 40, PLAIN END, TAR CTD, INCL EXCAV & BKFL	1	LF	\$250.00
	18" DIA. STEEL PIPE, SCHEDULE 40, PLAIN END, TAR CTD, INCL EXCAV & BKFL	1	LF	\$355.00
	24" DIA. STEEL PIPE SCHEDULE 40, PLAIN END, TAR CTS, INCL EXCAV & BKFL	1	LF	\$584.00
82410	4" DIA. STEEL PIPE, SCHEDULE 80, PLAIN END, TAR CTD, INCL EXCAV & BKFL	1	LF	\$97.00
	6" DIA. STEEL PIPE, SCHEDULE 80, PLAIN END, TAR CTD, INCL EXCAV & BKFL	1	LF	\$166.00
	<u>SEWAGE LIFT STATION</u> , PACKAGED (PCKG) SEWAGE LIFT STN, EXCL FENCING, EXTERNAL (EXT) PIPING (PNG) OR LIFT EQUIP BLDG			
83150	200,000 GPD, PCKG SEWAGE LIFT STN, EXCL FENCING OR EXT PNG	1	EA	\$347,100.00

APPENDIX A - SUPPORT FACILITIES UNIT COST TABLE (PART - II, Support Facilities).

NOTE: The Support Fac Unit Costs are for guidance only. Adjustment to these Unit Costs are allowed when local cost data are available with back-ups.

<u>CAT CODE</u>	<u>ITEM</u>	<u>QTY</u>	<u>UNIT</u>	<u>UNIT COST (\$/UNIT)</u>
	100 GPM, PCKG SEWAGE LIFT STN, EXCL FENCING OR EXT PNG	1	EA	\$302,430.00
	200 GPM, PCKG SEWAGE LIFT STN, EXCL FENCING OR EXT PNG	1	EA	\$388,160.00
	<u>SEWERAGE EJECTOR PUMP</u> - DUPLEX SYSTEM, W/ FIBERGLASS TANK, 135 GALLONS, OPERATING & LEVEL CONTROLS			
83150	174 GPM PUMP, 0.7 HP, 15' HEAD, 2" DISCHARGE, INCL FIBERGLASS TANK, CNTRLS, & TANK COVER	1	EA	\$4,473.00
	<u>SANITARY SEWER - STORM DRAINAGE (SD) MANHOLES (MH)</u>, CONCRETE CAST IN PLACE (CIP), INCL FRAMES & COVERS			
83210	4' x 4', 8" THICK SD MH, 4' DEEP CIP CONC, INCL FRAMES & COVERS, EXCL FTG, EXCAV, BKFL	1	EA	\$4,665.00
	4' x 4', 8" THICK SD MH, 6' DEEP CIP CONC, INCL FRAMES & COVERS, EXCL FTG, EXCAV, BKFL	1	EA	\$6,385.00
	4' DIA, 8" THICK SD MH, 8' DEEP CIP CONC, INCL FRAMES & COVERS, INCL BASE EXCAV & BKFL	1	EA	\$10,350.00
	4' DIA, 8" THICK SD MH, > 8' DEEP CIP CONC, INCL FRAMES & COVERS, INCL BASE EXCAV & BKFL	1	VLF	\$1,120.00
	4' DIA, TO 8' DEEP PRECAST CONC SD MH, INCL FRAMES & COVERS, INCL BASE EXCAV & BKFL	1	VLF	\$810.00
	4' DIA, > 8' DEEP PRECAST CONC SD MH, INCL FRAMES & COVERS, INCL BASE EXCAV & BKFL	1	VLF	\$850.00
	<u>CATCH BASIN (CB)</u> - CONCRETE PRECAST, INCLUDE MANHOLE, FRAMES, & COVER, BASE EXCAV & BKFL			
83210	5' INTERNAL DIA, 4' DEEP PRECAST CONC CB, INCL BASE EXCAV & BKFL	1	EA	\$4,782.00
	5' INTERNAL DIA, 6' DEEP PRECAST CONC CB, INCL BASE EXCAV & BKFL	1	EA	\$5,260.00
	<u>CURB INLET/ GUTTERMOUTH</u> - INCL CURB INLET FRAME, GRATE & CURB BOX; EXCL FOOTING, CB EXCAV & BKFL & PIPING OF DRAIN			
83210	24" x 36" LARGE, HEAVY DUTY CURB INLET, INCL FRAME, GRATE & CURB BOX, EXCL CB	1	EA	\$1,660.00
	<u>STORMWATER DRAINAGE (SD) PONDS</u> - INCLUDES FENCE, SEEDING SLOPES, PARTIAL LINER & EXCAVATION			
83210	1/8 ACRES, 5' DEEP SD POND, INCL SEEDING SLOPES, PARTIAL LINER & EXCAV	1	EA	\$24,860.00
	1/4 ACRES, 5' DEEP SD POND, INCL SEEDING SLOPES, PARTIAL LINER & EXCAV	1	EA	\$49,750.00
	3/8 ACRES, 5' DEEP SD POND, INCL SEEDING SLOPES, PARTIAL LINER & EXCAV	1	EA	\$74,820.00
	1/2 ACRES, 5' DEEP SD POND, INCL SEEDING SLOPES, PARTIAL LINER & EXCAV	1	EA	\$99,570.00
	<u>WATER DISTRIBUTION LINES</u> - CEMENT LINED DUCTILE IRON PIPE (DI), INCL MECHANICAL JOINT (MJ), EXCAVATION & BACKFILL, EXCL FITTINGS (FTGS)			
84210	4" DIA. 18' LENGTHS, CLASS 50 DI PIPE CEMENT LINED, INCL MJ, EXCAV, BKFL, EXCL FTGS	1	LF	\$49.60
	6" DIA. 18' LENGTHS, CLASS 50 DI PIPE CEMENT LINED, INCL MJ, EXCAV, BKFL, EXCL FTGS	1	LF	\$58.00

APPENDIX A - SUPPORT FACILITIES UNIT COST TABLE (PART - II, Support Facilities).

NOTE: The Support Fac Unit Costs are for guidance only. Adjustment to these Unit Costs are allowed when local cost data are available with back-ups.

<u>CAT CODE</u>	<u>ITEM</u>	<u>QTY</u>	<u>UNIT</u>	<u>UNIT COST (\$/UNIT)</u>
	10" DIA. 18' LENGTHS, CLASS 50 DI PIPE CEMENT LINED, INCL MJ, EXCAV, BKFL, EXCL FTGS	1	LF	\$94.00
	12" DIA. 18' LENGTHS, CLASS 50 DI PIPE CEMENT LINED, INCL MJ, EXCAV, BKFL, EXCL FTGS	1	LF	\$107.00
	18" DIA. 18' LENGTHS, CLASS 50 DI PIPE CEMENT LINED, INCL MJ, EXCAV, BKFL, EXCL FTGS	1	LF	\$172.00
	24" DIA. 18' LENGTHS, CLASS 50 DI PIPE CEMENT LINED, INCL MJ, EXCAV, BKFL, EXCL FTGS	1	LF	\$249.00
	<u>WATER DISTRIBUTION LINES - FIBERGLASS (FBGLS) PLASTIC PIPE, FILAMENT WOUND (FW), GENERAL SVC, INCL. EXCAVATION & BACKFILL</u>			
84210	2" DIA FBGLS PLASTIC PIPE, FILAMENT WOUND, GENERAL SVC, INCL EXCAV & BKFL	1	LF	\$46.70
	3" DIA FBGLS PLASTIC PIPE, FILAMENT WOUND, GENERAL SVC, INCL EXCAV & BKFL	1	LF	\$56.00
	4" DIA FBGLS PLASTIC PIPE, FILAMENT WOUND, GENERAL SVC, INCL EXCAV & BKFL	1	LF	\$65.00
	6" DIA FBGLS PLASTIC PIPE, FILAMENT WOUND, GENERAL SVC, INCL EXCAV & BKFL	1	LF	\$95.00
	10" DIA FBGLS PLASTIC PIPE, FILAMENT WOUND, GENERAL SVC, INCL EXCAV & BKFL	1	LF	\$174.00
	12" DIA FBGLS PLASTIC PIPE, FILAMENT WOUND, GENERAL SVC, INCL EXCAV & BKFL	1	LF	\$213.00
	<u>WATER DISTRIBUTION LINES - PLASTIC PIPE, PVC, INCL EXCAVATION & BACKFILL</u>			
84210	1" DIA PVC PIPE, SCHEDULE 40, INCL EXCAV & BKFL	1	LF	\$30.90
	2" DIA PVC PIPE, SCHEDULE 40, INCL EXCAV & BKFL	1	LF	\$41.10
	3" DIA PVC PIPE, SCHEDULE 40, INCL EXCAV & BKFL	1	LF	\$51.00
	4" DIA PVC PIPE, SCHEDULE 40, INCL EXCAV & BKFL	1	LF	\$59.00
	6" DIA PVC PIPE, SCHEDULE 40, INCL EXCAV & BKFL	1	LF	\$88.00
	10" DIA PVC PIPE, SCHEDULE 40, INCL EXCAV & BKFL	1	LF	\$176.00
	12" DIA PVC PIPE, SCHEDULE 40, INCL EXCAV & BKFL	1	LF	\$207.00
	<u>WATER DISTRIBUTION LINES - PLASTIC PIPE, PVC; INCL EXCAVATION & BACKFILL</u>			
84210	1" DIA PVC PIPE, SCHEDULE 80, INCL EXCAV & BKFL	1	LF	\$32.50
	2" DIA PVC PIPE, SCHEDULE 80, INCL EXCAV & BKFL	1	LF	\$45.00
	3" DIA PVC PIPE, SCHEDULE 80, INCL EXCAV & BKFL	1	LF	\$57.00
	4" DIA PVC PIPE, SCHEDULE 80, INCL EXCAV & BKFL	1	LF	\$66.00
	6" DIA PVC PIPE, SCHEDULE 80, INCL EXCAV & BKFL	1	LF	\$108.00
	10" DIA PVC PIPE, SCHEDULE 80, INCL EXCAV & BKFL	1	LF	\$201.00
	12" DIA PVC PIPE, SCHEDULE 80, INCL EXCAV & BKFL	1	LF	\$239.00

APPENDIX A - SUPPORT FACILITIES UNIT COST TABLE (PART - II, Support Facilities).

NOTE: The Support Fac Unit Costs are for guidance only. Adjustment to these Unit Costs are allowed when local cost data are available with back-ups.

<u>CAT CODE</u>	<u>ITEM</u>	<u>QTY</u>	<u>UNIT</u>	<u>UNIT COST (\$/UNIT)</u>
	<u>WATER DISTRBN LINE - PLASTIC PIPE, HIGH DENSITY POLYETHYLENE (HDPE), SINGLE (SGL) WALL, STRAIGHT (STR), WELDED, INCL EXCAV & BKFL</u>			
84210	1" DIA HPDE PIPE, DR 11, SGL WALL, STR, BASED ON 40' LENGTH & 1 WELD/JOINT, INCL EXCAV & BKFL	1	LF	\$8.20
	2" DIA HPDE PIPE, DR 11, SGL WALL, STR, BASED ON 40' LENGTH & 1 WELD/JOINT, INCL EXCAV & BKFL	1	LF	\$9.60
	3" DIA HPDE PIPE, DR 11, SGL WALL, STR, BASED ON 40' LENGTH & 1 WELD/JOINT, INCL EXCAV & BKFL	1	LF	\$10.30
	4" DIA HPDE PIPE, DR 11, SGL WALL, STR, BASED ON 40' LENGTH & 1 WELD/JOINT, INCL EXCAV & BKFL	1	LF	\$12.30
	6" DIA HPDE PIPE, DR 11, SGL WALL, STR, BASED ON 40' LENGTH & 1 WELD/JOINT, INCL EXCAV & BKFL	1	LF	\$21.80
	10" DIA HPDE PIPE, DR 11, SGL WALL, STR, BASED ON 40' LENGTH & 1 WELD/JOINT, INCL EXCAV & BKFL	1	LF	\$39.40
	12" DIA HPDE PIPE, DR 11, SGL WALL, STR, BASED ON 40' LENGTH & 1 WELD/JOINT, INCL EXCAV & BKFL	1	LF	\$53.00
	18" DIA HPDE PIPE, DR 11, SGL WALL, STR, BASED ON 40' LENGTH & 1 WELD/JOINT, INCL EXCAV & BKFL	1	LF	\$97.00
	24" DIA HPDE PIPE, DR 11, SGL WALL, STR, BASED ON 40' LENGTH & 1 WELD/JOINT, INCL EXCAV & BKFL	1	LF	\$104.00
	36" DIA HPDE PIPE, DR 11, SGL WALL, STR, BASED ON 40' LENGTH & 1 WELD/JOINT, INCL EXCAV & BKFL	1	LF	\$124.00
84472	<u>WATER PUMP, NONPOTABLE - FIRE PUMP, DIESEL (DSL), INCL. PUMP, CONTROLLER, FITTINGS (FTGS) & RELIEF VALVE (PRV), NO BLD</u>			
	500 GPM - 4" DSL PUMP, 125 PSI, 78 HP, INCL CONTROLLER, FTGS, & PRV, NO PUMP STN BLD	1	EA	\$59,630.00
	1000 GPM - 4" DSL PUMP, 100 PSI, 89 HP, INCL CONTROLLER, FTGS, & PRV, NO PUMP STN BLD	1	EA	\$59,060.00
	2000 GPM - 6" DSL PUMP, 100 PSI, 167 HP, INCL CONTROLLER, FTGS, & PRV, NO PUMP STN BLD	1	EA	\$77,620.00
	2500 GPM - 8" DSL PUMP, 150 PSI, 365 HP, INCL CONTROLLER, FTGS, & PRV, NO PUMP STN BLD	1	EA	\$106,330.00
84472	1000 GPM- 5" ELECT PUMP, 100 PSI, 86 HP, 3500 RPM, INCL CONTRLR, FTGS, & PRV, NO PUMP STN BLD	1	EA	\$37,590.00
	2000 GPM- 6" ELECT PUMP, 100 PSI, 167 HP, 1770 RPM, INCL CONTRLR, FTGS, & PRV, NO PUMP STN BLD	1	EA	\$49,150.00
	<u>WATER STORAGE TANK - ABOVEGROUND (AG) ELEVATED (ELEV) STEEL STORAGE (STOR) TANK, 100' HIGH TOWER, INCL SPREAD (SPRD) FOUNDATION (FDN), PAINTING (PNT), EXCL PIPES & PUMPS</u>			
84610	50,000 GA, ELEV STEEL STOR TANK, 100' HIGH TOWER, INCL SPRD FDN, PNT, EXCL PIPES & PUMPS	1	EA	\$293,090
	100,000 GA, ELEV STEEL STOR TANK, 100' HIGH TOWER, INCL SPRD FDN, PNT, EXCL PIPES & PUMPS	1	EA	\$442,160
	150,000 GA, ELEV STEEL STOR TANK, 100' HIGH TOWER, INCL SPRD FDN, PNT, EXCL PIPES & PUMPS	1	EA	\$662,690
	250,000 GA, ELEV STEEL STOR TANK, 100' HIGH TOWER, INCL SPRD FDN, PNT, EXCL PIPES & PUMPS	1	EA	\$1,188,100
	500,000 GA, ELEV STEEL STOR TANK, 100' HIGH TOWER, INCL SPRD FDN, PNT, EXCL PIPES & PUMPS	1	EA	\$2,112,930
	750,000 GA, ELEV STEEL STOR TANK, 100' HIGH TOWER, INCL SPRD FDN, PNT, EXCL PIPES & PUMPS	1	EA	\$2,563,520

APPENDIX A - SUPPORT FACILITIES UNIT COST TABLE (PART - II, Support Facilities).

NOTE: The Support Fac Unit Costs are for guidance only. Adjustment to these Unit Costs are allowed when local cost data are available with back-ups.

<u>CAT CODE</u>	<u>ITEM</u>	<u>QTY</u>	<u>UNIT</u>	<u>UNIT COST (\$/UNIT)</u>
	1,000,000 GA, ELEV STEEL STOR TANK, 100' HIGH TOWER, INCL SPRD FDN, PNT, EXCL PIPES & PUMPS	1	EA	\$3,673,430
	<u>GROUND STORAGE TANK (WATER) - ABOVEGROUND (AG) PRE-STRESSED CONCRETE TANK; INCL INTEGRAL FOUNDATION (FDN), EXCL PIPES AND PUMPS</u>			
84610	100,000 GA, AG PRE-STRESSED CONC WATER TANK, INCL INTEGRAL FDN, EXCL PIPES & PUMPS	1	EA	\$245,260
	250,000 GA, AG PRE-STRESSED CONC WATER TANK, INCL INTEGRAL FDN, EXCL PIPES & PUMPS	1	EA	\$473,670
	500,000 GA, AG PRE-STRESSED CONC WATER TANK, INCL INTEGRAL FDN, EXCL PIPES & PUMPS	1	EA	\$770,120
	1,000,000 GA, AG PRE-STRESSED CONC WATER TANK, INCL INTEGRAL FDN, EXCL PIPES & PUMPS	1	EA	\$1,160,540
	2,000,000 GA, AG PRE-STRESSED CONC WATER TANK, INCL INTEGRAL FDN, EXCL PIPES & PUMPS	1	EA	\$1,694,390
	4,000,000 GA, AG PRE-STRESSED CONC WATER TANK, INCL INTEGRAL FDN, EXCL PIPES & PUMPS	1	EA	\$2,697,400
	<u>RESERVOIR (RSVR), POTABLE WATER - GROUND LEVEL (GL) STEEL STORAGE (STOR) TANK, INCL 1' x 3' RING WALL FOUNDATION (FDN), EXCL PIPES & PUMPS</u>			
84620	250,000 GA, STEEL STOR TANK, GL, INCL 1' x 3' RING WALL FDN, EXCL PIPES & PUMPS	1	EA	\$472,530
	500,000 GA, STEEL STOR TANK, GL, INCL 1' x 3' RING WALL FDN, EXCL PIPES & PUMPS	1	EA	\$663,800
	1,000,000 GA, STEEL STOR TANK, GL, INCL 1' x 3' RING WALL FDN, EXCL PIPES & PUMPS	1	EA	\$1,046,340
	2,000,000 GA, STEEL STOR TANK, GL, INCL 1' x 3' RING WALL FDN, EXCL PIPES & PUMPS	1	EA	\$1,657,270
	4,000,000 GA, STEEL STOR TANK, GL, INCL 1' x 3' RING WALL FDN, EXCL PIPES & PUMPS	1	EA	\$3,369,650
84620	<u>UNDERGROUND (UGND) STORAGE (STOR) TANK - FIBERGLASS (FBGLS), DOUBLE (DBL) WALL, U.L. LISTED, INCLUDES MANWAYS, SLAB, & HOLD-DOWN STRAPS</u>			
	600 GA, FBGLS DBL WALL STOR TANK, UGND, U.L. LISTED, INCL MANWAYS, SLAB & HOLD-DN STRPS	1	EA	\$13,510.00
	1,000 GA, FBGLS DBL WALL STOR TANK, UGND, U.L. LISTED, INCL MANWAYS, SLAB & HOLD-DN STRPS	1	EA	\$18,560.00
	2,500 GA, FBGLS DBL WALL STOR TANK, UGND, U.L. LISTED, INCL MANWAYS, SLAB & HOLD-DN STRPS	1	EA	\$29,690.00
	4,000 GA, FBGLS DBL WALL STOR TANK, UGND, U.L. LISTED, INCL MANWAYS, SLAB & HOLD-DN STRPS	1	EA	\$36,570.00
	6,000 GA, FBGLS DBL WALL STOR TANK, UGND, U.L. LISTED, INCL MANWAYS, SLAB & HOLD-DN STRPS	1	EA	\$49,400.00
	8,000 GA, FBGLS DBL WALL STOR TANK, UGND, U.L. LISTED, INCL MANWAYS, SLAB & HOLD-DN STRPS	1	EA	\$57,950.00
	10,000 GA, FBGLS DBL WALL STOR TANK, UGND, U.L. LISTED, INCL MANWAYS, SLAB & HOLD-DN STRPS	1	EA	\$68,070.00
	12,000 GA, FBGLS DBL WALL STOR TANK, UGND, U.L. LISTED, INCL MANWAYS, SLAB & HOLD-DN STRPS	1	EA	\$82,130.00
	15,000 GA, FBGLS DBL WALL STOR TANK, UGND, U.L. LISTED, INCL MANWAYS, SLAB & HOLD-DN STRPS	1	EA	\$102,940.00

APPENDIX A - SUPPORT FACILITIES UNIT COST TABLE (PART - II, Support Facilities).

NOTE: The Support Fac Unit Costs are for guidance only. Adjustment to these Unit Costs are allowed when local cost data are available with back-ups.

<u>CAT CODE</u>	<u>ITEM</u>	<u>QTY</u>	<u>UNIT</u>	<u>UNIT COST (\$/UNIT)</u>
	20,000 GA, FBGLS DBL WALL STOR TANK, UGND, U.L. LISTED, INCL MANWAYS, SLAB & HOLD-DN STRPS	1	EA	\$126,010.00
	<u>ABOVE GROUND (AG) FUEL STORAGE (STOR) TANK - CONCRETE; INCLUDES PAD</u>			
84620	500 GA, CONCRETE STOR TANK, ABOVE GROUND, INCL PAD	1	EA	\$15,750.00
	1,000 GA, CONCRETE STOR TANK, ABOVE GROUND, INCL PAD	1	EA	\$21,160.00
	2,000 GA, CONCRETE STOR TANK, ABOVE GROUND, INCL PAD	1	EA	\$27,120.00
	4,000 GA, CONCRETE STOR TANK, ABOVE GROUND, INCL PAD	1	EA	\$33,870.00
	8,000 GA, CONCRETE STOR TANK, ABOVE GROUND, INCL PAD	1	EA	\$51,420.00
	12,000 GA, CONCRETE STOR TANK, ABOVE GROUND, INCL PAD	1	EA	\$68,070.00
	<u>ROADS/ LARGE PAVEMENTS - PLANT MIX ASPHALT CONCRETE (AC) SURFACE; EXCL EARTHWORK (CUT & FILL, CC 93410)</u>			
85110	1-1/2" THICK PLANT MIX AC PAVING, WEARING COURSE, EXCL EARTHWORK (CUT & FILL, CC 93410)	1	SY	\$9.90
	2" THICK PLANT MIX AC PAVING, WEARING COURSE, EXCL EARTHWORK (CUT & FILL, CC 93410)	1	SY	\$13.00
	3" THICK PLANT MIX AC PAVING, WEARING COURSE, EXCL EARTHWORK (CUT & FILL, CC 93410)	1	SY	\$18.90
	<u>RECYCLED PLANT MIX BITUMINOUS CONCRETE (BIT CONC) PAVEMENT (PVMT)</u>			
85110	PLANT MIXED BIT CONC, RECLAIMED PVMT IN STOCKPILE, 145 LB/CF	1	TON	\$69.00
	PLANT MIXED BIT CONC, RECYCLED PVMT OLD/NEW RATIO 70:30	1	TON	\$75.00
	<u>UNREINFORCED CONC PAVEMENTS (PVMT), FIXED FORM, 12' PASS, INCL JOINTS, FINISHINGS, & CURING EXCL. EARTHWORK</u>			
85110	6" THICK, UNREINF PVMT, 4500 PSI, FIXED FORM, 12' PASS, INCL JOINTS, FIN & CUR, EXCL EARTHWRK	1	SY	\$32.50
	8" THICK, UNREINF PVMT, 4500 PSI, FIXED FORM, 12' PASS, INCL JOINTS, FIN & CUR, EXCL EARTHWRK	1	SY	\$44.00
	10" THICK, UNREINF PVMT, 4500 PSI, FIXED FORM, 12' PASS, INCL JOINTS, FIN & CUR, EXCL EARTHWRK	1	SY	\$55.00
	12" THICK, UNREINF PVMT, 4500 PSI, FIXED FORM, 12' PASS, INCL JOINTS, FIN & CUR, EXCL EARTHWRK	1	SY	\$61.00
	16" THICK, UNREINF PVMT, 4500 PSI, FIXED FORM, 12' PASS, INCL JOINTS, FIN & CUR, EXCL EARTHWRK	1	SY	\$83.00
	<u>REINFORCED CONC PAVEMENTS (PVMT), FIXED FORM, 12' PASS, INCL JOINTS, FINISHINGS, & CURING EXCL. EARTHWORK</u>			
85110	6" THK, REINF CONC PVMT, 4500 PSI, FIXED FORM, 12' PASS, INCL JOINTS, FIN & CUR, EXCL EARTHWRK	1	SY	\$48.90
	8" THK, REINF CONC PVMT, 4500 PSI, FIXED FORM, 12' PASS, INCL JOINTS, FIN & CUR, EXCL EARTHWRK	1	SY	\$59.00

APPENDIX A - SUPPORT FACILITIES UNIT COST TABLE (PART - II, Support Facilities).

NOTE: The Support Fac Unit Costs are for guidance only. Adjustment to these Unit Costs are allowed when local cost data are available with back-ups.

<u>CAT CODE</u>	<u>ITEM</u>	<u>QTY</u>	<u>UNIT</u>	<u>UNIT COST (\$/UNIT)</u>
	10" THK, REINF CONC PVMT, 4500 PSI, FIXED FORM, 12' PASS, INCL JOINTS, FIN & CUR, EXCL ERTHWK	1	SY	\$70.00
	<u>CAST IN PLACE (CIP) CONCRETE CURB & GUTTER (C&G), STRAIGHT, WOOD FORM, NO EARTHWORK INCLUDED</u>			
85110	6" HI CURB, 6" THK GUTTER, 24" WIDE, CIP CONC, STR WOOD FORMS, 0.055 C.Y. / LF, EXCL ERTHWK	1	LF	\$31.50
	6" HI CURB, 6" THK GUTTER, 30" WIDE, CIP CONC, STR WOOD FORMS, 0.066 C.Y. / LF, EXCL ERTHWK	1	LF	\$59.00
	PRECAST CONC CURBS 6" HI x 18" WIDE, NO ERTHWK INCLUDED	1	LF	\$70.00
	<u>BASE COURSE DRAINAGE LAYERS for ROADWAYS & LARGE PAVED AREAS - COMPACTED, EXCL EARTHWORK (ERTHWK)</u>			
85110	1-1/2" CRUSHED STONE BASE TO 4" DEEP, COMPACTED, INCL TRANS & EQPT, EXCL ERTHWK	1	SY	\$7.00
	1-1/2" CRUSHED STONE BASE TO 6" DEEP, COMPACTED, INCL MATERIAL & TRANS, EXCL ERTHWK	1	SY	\$9.90
	1-1/2" CRUSHED STONE BASE TO 8" DEEP, COMPACTED, INCL MATERIAL & TRANS, EXCL ERTHWK	1	SY	\$13.00
	1-1/2" CRUSHED STONE BASE TO 12" DEEP, COMPACTED, INCL MATERIAL & TRANS, EXCL ERTHWK	1	SY	\$18.60
	<u>BANK RUN GRAVEL BASE COURSE, SPREAD & COMPACTED, INCL TRANS & EQPT, EXCL ERTHWK</u>			
85110	BANK RUN GRAVEL BASE, 6" DEEP, SPREAD & COMPACTED, INCL TRANS & EQPT, EXCL ERTHWK	1	SY	\$6.70
	BANK RUN GRAVEL BASE, 9" DEEP, SPREAD & COMPACTED, INCL TRANS & EQPT, EXCL ERTHWK	1	SY	\$9.90
	BANK RUN GRAVEL BASE, 12" DEEP, SPREAD & COMPACTED, INCL TRANS & EQPT, EXCL ERTHWK	1	SY	\$13.00
	<u>PLANT MIXED BITUMINOUS CONCRETE BASE COURSE, EXCL EARTHWORK</u>			
85110	PLANT MIXED BITUMINOUS CONC BASE, 4" THICK, EXCL ERTHWK	1	SY	\$23.10
	PLANT MIXED BITUMINOUS CONC BASE, 6" THICK, EXCL ERTHWK	1	SY	\$33.20
	PLANT MIXED BITUMINOUS CONC BASE, 8" THICK, EXCL ERTHWK	1	SY	\$44.50
	PLANT MIXED BITUMINOUS CONC BASE, 10" THICK, EXCL ERTHWK	1	SY	\$55.00
	<u>SURFACE TREATMENTS</u>			
85110	TACK COAT, ELMUSION, 15 GALLONS/SY	1	SY	\$2.00
	SLURRY SEAL, TYPE II, 12 lb AGGREGATE/SY	1	SY	\$5.90
	PAVEMENT MARKINGS, ACRYLLIC WATERBORNE, 4" WIDE WHITE OR YELLOW, < 3000 LF	1	LF	\$0.40

APPENDIX A - SUPPORT FACILITIES UNIT COST TABLE (PART - II, Support Facilities).

NOTE: The Support Fac Unit Costs are for guidance only. Adjustment to these Unit Costs are allowed when local cost data are available with back-ups.

<u>CAT CODE</u>	<u>ITEM</u>	<u>QTY</u>	<u>UNIT</u>	<u>UNIT COST (\$/UNIT)</u>
	<u>SIDEWALKS & WALKWAYS</u> - PEDESTRIAN SIDEWALKS & WALKWAYS, WITH BASE COURSE. SEE CC 85110 FOR DRIVEWAYS & ROADS			
85220	4" THICK CAST IN PLACE (CIP) CONC, 6' x 6' -W 1.4 x W1.4 MESH, 3000 PSI, BROMMED FINISH, W/ BASE	1	SY	\$63.00
	2-1/2" ASPHALT CONCRETE W/ BASE	1	SY	\$21.10
	<u>RAILROAD (RR) TRACKS W/TIES AND BALLAST</u> FOR STANDARD GAUGE. TRACK IS DEFINED AS A SINGLE PAIR OF RAILS,			
86010	RR TRACKS, 100 LB Rail, LEVEL GRADE, W/ WOOD TIES, INCL BALLASTS, CLIPS, ANGLE BARS & BOLTS.	1	LF	\$290.00
	<u>STORM WATER DRAINAGE SEWER/PIPING</u> - INCL EXCAV & BKFL. TYPICALLY STORM WATER DRAINAGE SYSTEM WILL CONSISTS OF DRAINAGE INLET, RETENTION BASINS, PIPELINES, ACCESS MANHOLES, & OTHER COMPONENTS			
	<u>CORRUGATED METAL PIPE (CMP), 16 GA,</u> GALVANIZED (GALV) & BITUMINOUS (BITUMN) COATED (CTD)			
87110	8" DIA CMP PIPE, GALV & BITUMN CTD, 16 GA, w/ PAVED INVERT, 20' LONG, INCL EXCAV & BKFL	1	LF	\$27.40
	10" DIA CMP PIPE, GALV & BITUMN CTD, 16 GA, w/ PAVED INVERT, 20' LONG, INCL EXCAV & BKFL	1	LF	\$32.50
	12" DIA CMP PIPE, GALV & BITUMN CTD, 16 GA, w/ PAVED INVERT, 20' LONG, INCL EXCAV & BKFL	1	LF	\$38.90
	15" DIA CMP PIPE, GALV & BITUMN CTD, 16 GA, w/ PAVED INVERT, 20' LONG, INCL EXCAV & BKFL	1	LF	\$42.70
	18" DIA CMP PIPE, GALV & BITUMN CTD, 16 GA, w/ PAVED INVERT, 20' LONG, INCL EXCAV & BKFL	1	LF	\$48.30
	24" DIA CMP PIPE, GALV & BITUMN CTD, 16 GA, w/ PAVED INVERT, 20' LONG, INCL EXCAV & BKFL	1	LF	\$59.00
	30" DIA CMP PIPE, GALV & BITUMN CTD, 16 GA, w/ PAVED INVERT, 20' LONG, INCL EXCAV & BKFL	1	LF	\$87.00
	36" DIA CMP PIPE, GALV & BITUMN CTD, 16 GA, w/ PAVED INVERT, 20' LONG, INCL EXCAV & BKFL	1	LF	\$99.00
	60" DIA CMP PIPE, GALV & BITUMN CTD, 16 GA, w/ PAVED INVERT, 20' LONG, INCL EXCAV & BKFL	1	LF	\$198.00
	<u>NON-REINFORCED (NR) CONCRETE PIPE, EXTRA STRENGTH,</u> INCL EXCAV & BKFL			
87110	6" DIA NR CONC PIPE, EXTRA STRENGHT, B&S OR T&G JOINTS, INCL EXCAV & BKFL	1	LF	\$39.40
	10" DIA NR CONC PIPE, EXTRA STRENGHT, B&S OR T&G JOINTS, INCL EXCAV & BKFL	1	LF	\$42.20
	12" DIA NR CONC PIPE, EXTRA STRENGHT, B&S OR T&G JOINTS, INCL EXCAV & BKFL	1	LF	\$46.70
	18" DIA NR CONC PIPE, EXTRA STRENGHT, B&S OR T&G JOINTS, INCL EXCAV & BKFL	1	LF	\$63.00
	24" DIA NR CONC PIPE, EXTRA STRENGHT, B&S OR T&G JOINTS, INCL EXCAV & BKFL	1	LF	\$90.00
	36" DIA NR CONC PIPE, EXTRA STRENGHT, B&S OR T&G JOINTS, INCL EXCAV & BKFL	1	LF	\$174.00
	<u>REINFORCED CONCRETE PIPE (RCP), CLASS 3,</u> INCL EXCAV, BKFL & GASKETS			
87110	12" DIA RCP, 6' LENGHTS, CLASS-3, INCL EXCAV, BKFL & GASKETS	1	LF	\$55.00

APPENDIX A - SUPPORT FACILITIES UNIT COST TABLE (PART - II, Support Facilities).

NOTE: The Support Fac Unit Costs are for guidance only. Adjustment to these Unit Costs are allowed when local cost data are available with back-ups.

<u>CAT CODE</u>	<u>ITEM</u>	<u>QTY</u>	<u>UNIT</u>	<u>UNIT COST (\$/UNIT)</u>
	18" DIA RCP, 6' LENGHTS, CLASS-3, INCL EXCAV, BKFL & GASKETS	1	LF	\$70.00
	24" DIA RCP, 8' LENGHTS, CLASS-3, INCL EXCAV, BKFL & GASKETS	1	LF	\$95.00
	36" DIA RCP, 8' LENGHTS, CLASS-3, INCL EXCAV, BKFL & GASKETS	1	LF	\$173.00
	60" DIA RCP, 8' LENGHTS, CLASS-3, INCL EXCAV, BKFL & GASKETS	1	LF	\$344.00
	<u>SELECTIVE DEMOLITION</u> (DEMO) OF WATER & SEWER PIPINGS & FITTINGS (FTG), EXCL EXCAV			
87110	DEMO CONC PIPE, 42"- 48" DIA & FTG, EXCL EXCAV	1	LF	\$59.00
	DEMO CONC PIPE, 60"- 84" DIA & FTG, EXCL EXCAV	1	LF	\$71.00
	DEMO DUCTILE IRON PIPE, 6"- 12" DIA, EXCL EXCAV	1	LF	\$22.20
	DEMO DUCTILE IRON PIPE, 14"- 24" DIA, EXCL EXCAV	1	LF	\$32.50
	DEMO COPPER PIPE, 3/4" - 2" DIA, EXCL EXCAV	1	LF	\$1.90
	DEMO COPPER PIPE, 2 1/2" - 3" DIA, EXCL EXCAV	1	LF	\$5.10
	<u>INDUSTRIAL CHAIN LINK FENCING & WALLS</u>			
	<u>GALVANIZED (GALV) STEEL FENCE, SCHEDULE (SCH) 40, INCL EXCAV & CONCRETE (CONC)</u>			
87210	4' HI, 9 GA GALV STEEL 3-STRANDS BARB WIRE, SCH 40, W/ 2" POSTS @ 10' OC, INCL EXCAV & CONC	1	LF	\$24.30
	6' HI, 9 GA GALV STEEL 3-STRANDS BARB WIRE, SCH 40, W/ 2" POSTS @ 10' OC, INCL EXCAV & CONC	1	LF	\$34.40
	8' HI, 9 GA GALV STEEL 3-STRANDS BARB WIRE, SCH 40, W/ 2" POSTS @ 10' OC, INCL EXCAV & CONC	1	LF	\$44.50
	10' HI, 9 GA GALV STEEL 3-STRANDS BARB WIRE, SCH 40, W/ 2" POSTS @ 10' OC, INCL EXCAV & CONC	1	LF	\$52.00
	FENCE TOPPING, STAINLESS STEEL, HELICAL RAZOR TAPE, 18" DIA x 18" SPACING	100	LF	\$227.00
	<u>ENTRANCE GATES, CHAIN LINK (CL) FENCE GATE, INDUSTRIAL</u>			
87250	CL FENCE GATE 4' WIDE, 6' HIGH, 9 GA WIRE, SCH-20, W/ 2" POSTS, INCL EXCAV & CONC	1	EA	\$445.00
	CL FENCE GATE 12' OPENING, SINGLE (SGL) SWING, 6' HIGH, MANUAL OPRN, INCL EXCAV & CONC,	1	EA	\$974.00
	MOTOR OPERATOR FOR 12' OPENING, 6' HIGH, SGL SWING CL GATE	1	EA	\$4,923.00
	CL FENCE GATE 24' OPNG, PAIR, DOUBLE (DBL) SWING, 6' HIGH, MANUAL OPRN, INCL EXCAV & CONC,	1	EA	\$1,913.00
	MOTOR OPERATOR FOR 24' OPENING, PAIR, 6' HIGH, DBL SWING CL GATE	1	EA	\$4,923.00
	CL FENCE GATE 36' OPENING, PAIR, DBL SLIDING, 6' HIGH, MANUAL OPRN, INCL EXCAV & CONC,	1	EA	\$2,391.00
	MOTOR OPERATOR FOR 36' OPENING, PAIR, 6' HIGH, DBL SLIDING GATE	1	EA	\$6,638.00

APPENDIX A - SUPPORT FACILITIES UNIT COST TABLE (PART - II, Support Facilities).

NOTE: The Support Fac Unit Costs are for guidance only. Adjustment to these Unit Costs are allowed when local cost data are available with back-ups.

<u>CAT CODE</u>	<u>ITEM</u>	<u>QTY</u>	<u>UNIT</u>	<u>UNIT COST (\$/UNIT)</u>
	<u>CHAIN LINK (CL) FENCE GATE, INDUSTRIAL, INCL EXCAV & CONC</u>			
87250	4' HIGH FENCE, 1-5/8" FRAME, GATE 3' WIDE, 6' HIGH, GALV STEEL, INCL EXCAV, IN CONC	1	EA	\$322.00
	6' HIGH FENCE, 1-5/8" FRAME, GATE 3' WIDE, 6' HIGH, GALV STEEL, INCL EXCAV, IN CONC	1	EA	\$461.00
	8' HIGH FENCE, 1-5/8" FRAME, GATE 3' WIDE, 6' HIGH, GALV STEEL, INCL EXCAV, IN CONC	1	EA	\$613.00
	GATE 10' OPENING, DOUBLE SWING GATE, 8' HIGH, INCL EXCAV, POSTS & HARDWARE IN CONC	1	EA	\$1,969.00
	GATE 24' WIDE, 8' HIGH, OVERHEAD SLIDE, CANTILEVER TYPE, INCL EXCAV, IN CONC	1	EA	\$10,180.00
	<u>SELECTIVE DEMOLITION - CHAIN LINK FENCE & GATES</u>			
87250	DEMO 3' - 4' HIGH FENCE	1	LF	\$2.20
	DEMO 5' HIGH FENCE	1	LF	\$2.40
	DEMO 12' HIGH FENCE	1	LF	\$5.70
	DEMO 3' - 4' WIDE GATE	1	LF	\$75.00
88040	<u>AT/FP VEHICULAR BARRIER - SEE AT THE END</u>			
	<u>FIRE HYDRANTS (FH), 2-WAY, 4-1/2" CUTOFF VALVE, INCL MECHANICAL JOINTS, EXCAV & BKFL</u>			
89240	FIRE HYDRANT 4-6" DEPTH, 2-WAY, 4-1/2" CUT-OFF VALVE, INCL MECH JOINTS, EXCAV & BKFL	1	EA	\$5,795.00
	FIRE HYDRANT 6" DEPTH, 2-WAY, 4-1/2" CUT-OFF VALVE, INCL MECH JOINTS, EXCAV & BKFL	1	EA	\$6,048.00
	FIRE HYDRANT 8" DEPTH, 2-WAY, 4-1/2" CUT-OFF VALVE, INCL MECH JOINTS, EXCAV & BKFL	1	EA	\$6,329.00
	<u>SITE CLEARING & GRADING - CLEARING & GRUBBING</u>			
93210	BRUSH AND STUMP, SURFACE ITEM CLEARING	1	SY	\$1.70
	CLEAR & GRUB, LIGHT TREES TO 6" DIA - CUT, CHIP & HAUL	1	ACRE	\$5,697.00
	CLEAR & GRUB, MEDIUM TREES TO 12" DIA, CUT, CHIP & HAUL	1	ACRE	\$8,158.00
	CLEAR & GRUB, HEAVY TREES TO 24" DIA, CUT, CHIP & HAUL	1	ACRE	\$19,140.00
	GRUB STUMPS & REMOVE, TREES TO 12" DIA	1	ACRE	\$6,278.00
	<u>SITE CLEARING & GRADING - GRADING</u>			

APPENDIX A - SUPPORT FACILITIES UNIT COST TABLE (PART - II, Support Facilities).

NOTE: The Support Fac Unit Costs are for guidance only. Adjustment to these Unit Costs are allowed when local cost data are available with back-ups.

<u>CAT CODE</u>	<u>ITEM</u>	<u>QTY</u>	<u>UNIT</u>	<u>UNIT COST (\$/UNIT)</u>
93210	ROUGH GRADING, DUMPED MATERIAL SPREAD BY DOZER, NO COMPACTION	1	LINEAR CY	\$2.90
	FINE GRADING, GRANULER BUBBASE FOR PAVING, +/- 1" COMPACTION, 3 PASSES W/ DOZER, 6" LIFTS	1	SY	\$2.30
	<u>SITE CLEARING & GRADING - BORROW</u> , INCL LOAD AT PIT & HAUL, 2 MILES ROUNFD TRIP, NO COMPACTION			
93210	FLY ASH, SPREAD w/ 200 HP DOZER, INCL LOAD AT PIT & HAUL 2 MI ROUND TRIP, NO CMPCT	1	CY	\$36.50
	BANK RUN GRAVEL, SPREAD w/ 200 HP DOZER, INCL LOAD AT PIT & HAUL 2 MI ROUND TRIP, NO CMPCT	1	CY	\$46.70
	SAND, SPREAD w/ 200 HP DOZER, INCL LOAD AT PIT & HAUL 2 MI ROUND TRIP, NO CMPCT	1	CY	\$66.00
	GRAVEL, SPREAD w/ 200 HP DOZER, INCL LOAD AT PIT & HAUL 2 MI ROUND TRIP, NO CMPCT	1	CY	\$39.40
	COMMON FILL, SPREAD w/ 200 HP DOZER, INCL LOAD AT PIT & HAUL 2 MI ROUND TRIP, NO CMPCT	1	CY	\$33.20
	SILT CLAY, SPREAD w/ 200 HP DOZER, INCL LOAD AT PIT & HAUL 2 MI ROUND TRIP, NO CMPCT	1	CY	\$19.10
	<u>LANDSCAPE AND PLANTING</u>			
	<u>SOIL PREPARATION - TOP SOIL</u>			
93220	MIX & SPREAD CONDITIONED SOIL, SPREAD 4" DEEP BY HAND	1	SY	\$10.30
	SPREAD FERTILIZER, 0.2#/SY BY TRACTOR SPREADER	1,000	SF	\$10.50
	HAUL & SPREAD TOP SOIL, TRUCK DUMPED, INCL MATERIAL, TRANSPORT & PLACEMENT	1	CY	\$7.90
	STRIP TOPSOIL & STOCKPILE ON SITE, 6" DEEP BY 200 HP DOZER, 200' HAUL	1	SY	\$0.50
	<u>SOIL PREPARATION - MULCHING</u>			
93220	HAY, 1" DEEP, POWER MULCHER, LARGE AREA	1,000	SY	\$74.00
	PEAT MOSS, 1" DEEP, TRACTOR SPREADER	1,000	SY	\$394.00
	WOOD CHIPS, 2" DEEP, SKID STEER LOADER	1,000	SY	\$376.00
	WOOD CHIPS, 2" DEEP, HAND SPREAD, SMALL AREA	1	SY	\$4.60
	<u>LANDSCAPE & PLANTING - GRASS</u>			
93220	SEEDING - TALL FESCUE, 5.5 LB/1000 SF, TRACTOR SPREADER	1,000	SF	\$35.00
	SEEDING - BLUE GRASS, 4LB/1000 SF, HYDRO OR AIR SEEDING W/ FERTILIZER	1,000	SF	\$66.00
	SODDING - 1" DEEP BLUEGRASS SOD ON LEVEL GROUND	1,000	SF	\$624.00

APPENDIX A - SUPPORT FACILITIES UNIT COST TABLE (PART - II, Support Facilities).

NOTE: The Support Fac Unit Costs are for guidance only. Adjustment to these Unit Costs are allowed when local cost data are available with back-ups.

<u>CAT CODE</u>	<u>ITEM</u>	<u>QTY</u>	<u>UNIT</u>	<u>UNIT COST (\$/UNIT)</u>
	<u>LANDSCAPE & PLANTING - PLANTING BED PREPARATION</u>			
93220	EXCAVATE PLANTING PIT, SANDY SOIL, 1/2 CY, BACKHOE	1	CY	\$11.80
	MIX PLANTING SOIL, INCLUDES LOAM, SKID STEER LOADER	1	CY	\$71.00
	REMOVE SOD, ARTICULATED LOADER	1	SY	\$0.70
	<u>LANDSCAPE & PLANTING - GROUND COVER</u>			
93220	PLANTAIN LILY (Hemerocallis Hybrids), ZONE 4, CONTAINER, 1 QUART	1	EA	\$34.40
	MOSS OR CREEPING PHLOX (Phlox Subulata), ZONE 4, CONTAINER, 1 GALLON	1	EA	\$34.40
	STONECROP (Sedum), ZONE 4, CONTAINER, 1 GALLON	1	EA	\$19.40
	<u>LANDSCAPE & PLANTING - SHRUBS, BALLED & BURLAPED (B&B)</u>			
93220	AZALEA EVERGREEN HYBRIDS, ZONE 6, CONTAINER BALLED & BURLAPED, 3 GALLON	1	EA	\$23.10
	COMMON BOXWOOD (Buxus Sempervirens), ZONE 5, CONTAINER BALLED & BURLAPED, 18" TO 24"	1	EA	\$60.00
	WINGED BURNING BUSH (Eunymus Alatus), ZONE 4, CONTAINER BALLED & BURLAPED, 18" - 24"	1	EA	\$31.50
	BLUE HOLLY (Ilex Meserve Blue Holly Hybr), ZONE 5, CONTAINER BALLED & BURLAPED, 18" - 24"	1	EA	\$32.00
	PJM RHODODENDRON, ZONE 4, CONTAINER BALLED & BURLAPED, 18" - 24"	1	EA	\$53.00
	<u>LANDSCAPE & PLANTING - DECIDUOUS TREES</u>			
93220	RED MAPLE (Acer Rubrum), ZONE 4, CONTAINER BALLED & BURLAPED, 1-1/2" To 2" CALIPER	1	EA	\$269.00
	AMERICAN BEECH (Fagus Grandiflora), ZONE 3, CONTAINER B&B, 1-1/2" To 1-3/4" CALIPER	1	EA	\$338.00
	LOMBARDY POPLAR (Populus Nigra Italica), ZONE 4, CONTAINER BALLED & BURLAPED, 5 GALLON	1	EA	\$31.50
	RED OAK (Quercus Rubra), ZONE 4, CONTAINER BALLED & BURLAPED, 5 GALLON	1	EA	\$37.60
	<u>LANDSCAPE - SUBSURFACE DRIP IRRIGATION (SDI)</u>			
93220	SDI , LOOPED GRID, REGULAR AREA, LARGE LINE, HAND BURY, PRESSURE COMP PREINSERTED EMITTER	1	LF	\$1.00
	SDI - IRREGULAR IRRIGATED AREA, HAND BURY, PRESSURE COMP PREINSERTED EMITTER IN TRENCH	1	LF	\$0.50
	UNDERGROUND SPRINKLERS IRRIGATION FOR 9 HOLE GOLF COURSE w/ FULLY AUTOMATIC SYS	1	EA	\$280,160.00
	UNDERGROUND SPRINKLERS IRRIGATION, RESIDENTIAL SYSTEM FOR LAWNS, 1-1/2" SUPPLY	1	SF	\$1.60

APPENDIX A - SUPPORT FACILITIES UNIT COST TABLE (PART - II, Support Facilities).

NOTE: The Support Fac Unit Costs are for guidance only. Adjustment to these Unit Costs are allowed when local cost data are available with back-ups.

<u>CAT CODE</u>	<u>ITEM</u>	<u>QTY</u>	<u>UNIT</u>	<u>UNIT COST (\$/UNIT)</u>
	DEMOLITION W/ DISPOSAL, BUILDING - INCL 20 MILE HAUL, EXCL FOUNDATION DEMO, HAZARDOUS MATERIAL DEMO, SALVAGE/RECYCLE & DUMP FEES. VOLUME (CF) IS THE VOLUME OF THE ENTIRE BUILDING			
93310	DEMO CONCRETE STRUCTURE (LARGE URBAN PROJECT); CF IS THE VOLUME OF THE ENTIRE BLDG	1	CF	\$0.60
	DEMO STEEL FRAME BUILDING - SMALL OR SINGLE BLDG; CF IS THE VOLUME OF THE ENTIRE BLDG	1	CF	\$0.50
	MASONRY OR WOOD FRAME - SMALL OR SINGLE; CF IS THE VOLUME OF THE ENTIRE BLDG	1	CF	\$0.50
	SELECTIVE DEMOLITION - BUILDING. EXCL DISPOSAL COST, RUBBISH HANDLING COSTS, SALVAGE & DUMP FEES			
93310	DEMO CONC FLOOR SLAB ON GRADE, PLAIN CONC, TO 6" THK, EXCL DISP, SALVAGE & DUMP COSTS	1	SF	\$8.40
	GUTTING COMMERCIAL BLDG. INTERIOR, NO HAZARDOUS MATERIAL DEMO OR DUMPSTER FEES	1	SF	\$12.80
	LEAD BASED PAINT (LBP) REMOVAL BY CHEMICALS & DISPOSAL, CABINETS & WALLS SIMPLE DESIGN	1	SF	\$20.00
	NOTE: LBP IS NOT REQUIRED TO BE ABATED PRIOR TO OR AS A PART OF THE BLDG DEMOLITION, UNLESS SPECIFICALLY REQUIRED IN COMPLIANCE WITH EM 385-1-1. UNLESS OTHERWISE RESTRICTED, MATERIALS COATED W/ LBP MAY BE PLACES IN THE LANDFILL.			
	RUBBISH HANDLING- DISPOSAL COST			
93310	DUMPSTER FEE, AVERAGE OF ALL SIZES (Note: TO BE ADD TO DEMO COST)	1	TON	\$119.00
	RUBBISH HANDLING, 50' HAUL, INCL LOADING, HAUL TO CHUTE & DUMPING TO CHUTE	1	CY	\$46.10
	SELECTIVE BUILDING MATERIAL RECYCLE, INCL SALVAGE LABOR			
93310	SALVAGE WOOD FLOOR, INCL SALVAGE LABOR FOR DENAILING & PACKAGING	1	SF	\$6.10
	SALVAGE CARPET, INCL SALVAGE LABOR	1	SF	\$0.50
	DEMOLITION - PAVEMENTS. REMOVE PAVEMENT & CURB, EXCL HAULING & DISPOSAL FEES			
93310	DEMO & REMOVE CONC PVMT & CURB, TO 6" THK, MESH REINF, EXCL HAULING & DISPOSAL FEE	1	SY	\$19.10
	DEMO & REMOVE W/ BACKHOE PLAIN CONC, 7" To 24" THK, EXCL HAULING & DISPOSAL FEE	1	CY	\$147.00
	DEMO & REMOVE ROD REINF CONC, 7" To 24", EXCL HAULING & DISPOSAL FEE	1	CY	\$202.00
	DEMO & REMOVE BITUMINOUS PVMT, TO 3" THK, EXCL HAULING & DISPOSAL FEE	1	SY	\$7.00
	REMOVE PLAIN CONC CURBS, EXCL HAULING & DISPOSAL FEE	1	LF	\$6.40
	DEMO & REMOVE BITUMINOUS SIDEWALK, 2-1/2" THK, EXCL HAULING & DISPOSAL FEE	1	SY	\$7.10
	MINOR SITE DEMO, EXCL HAULING & DISPOSAL FEE			

APPENDIX A - SUPPORT FACILITIES UNIT COST TABLE (PART - II, Support Facilities).

NOTE: The Support Fac Unit Costs are for guidance only. Adjustment to these Unit Costs are allowed when local cost data are available with back-ups.

<u>CAT CODE</u>	<u>ITEM</u>	<u>QTY</u>	<u>UNIT</u>	<u>UNIT COST (\$/UNIT)</u>
93310	DEMO & REMOVE PLAIN CONC SLAB ON GRADE, EXCL HAULING & DISPOSAL FEE	1	SY	\$19.30
	DEMO & REMOVE ROD REINF CONC SLAB ON GRADE, 8" THK, EXCL HAULING & DISPOSAL FEE	1	CY	\$249.00
	DEMO & REMOVE PLAIN CONC, 4" THK, EXCL HAULING & DISPOSAL FEE	1	SY	\$14.40
	<u>CUT AND FILL - BCY = BANKED CUBIC YARDS, ECY = EMBANKMENT CY, LCY = LOOSE CY</u>			
	<u>GRADING, COMMON EARTH:</u>			
93410	FINE GRADING FOR SMALL IRREGULAR AREAS, TO 15,000 SY	1	SY	\$3.60
	FINE GRADING FOR ROADWAYS, BASE OR LEVELLING COURSE, LARGE AREA 6,000 SY OR MORE	1	SY	\$1.10
	SPREAD FILL FROM STOCKPILE W/ FRONT LOADER, 200 H.P DOZER, TO 300' HAUL, NO COMPACTION	1	LCY	\$6.60
	<u>CUT AND FILL: BCY = BANKED CUBIC YARDS, ECY = EMBANKMENT CY, LCY = LOOSE CY</u>			
	<u>EXCAVATION, COMMON EARTH:</u>			
93410	EXCAVATION W/ 105 H.P. BULK DOZER, OPEN SITE 150' HAUL	1	BCY	\$6.60
	EXCAVATION W/ 300 H.P. BULK DOZER, OPEN SITE 150' HAUL	1	BCY	\$4.40
	EXCAVATION W/ 700 H.P. BULK DOZER, OPEN SITE 150' HAUL	1	BCY	\$2.20
	EXCAVATION TRENCH, 18" WIDE, 6' DEEP, OPEN SITE, BY CHAIN TRENCHER, 12 HP	1	BCY	\$1.50
	EXCAVATION TRENCH BY HAND W/ PICK & SHOVEL, 2' TO 6' DEEP, HEAVY SOIL, NO DEWATERING	1	BCY	\$139.00
93410	HAUL BY 8 CY TRUCK, CYCLE 6 MILES AT 30 MPH, 10 MIN WAIT-LOAD-UNLOAD, NO LOADING EQUIP	1	LCY	\$6.40
	HAUL BY 8 CY TRUCK, CYCLE 4 MILES AT 30 MPH, 10 MIN WAIT-LOAD-UNLOAD, NO LOADING EQUIP	1	LCY	\$5.20
	HAUL BY 8 CY TRUCK, CYCLE 4 MILES AT 30 MPH, 15 MIN WAIT-LOAD-UNLOAD, NO LOADING EQUIP	1	LCY	\$6.60
	HAUL BY 12 CY TRUCK, CYCLE 10 MILES AT 30 MPH, 25 MIN WAIT-LOAD-UNLOAD, NO LOADING EQUIP	1	LCY	\$12.40
	HAUL BY 16.5 CY TRUCK, CYCLE 10 MILES AT 30 MPH, 30 MIN WAIT-LOAD-UNLOAD, NO LOADING EQUIP	1	LCY	\$10.50
	HAUL BY 20 CY TRUCK, CYCLE 8 MILES AT 30 MPH, 30 MIN WAIT-LOAD-UNLOAD, NO LOADING EQUIP	1	LCY	\$8.00
	HAUL BY 12 CY TRUCK, EXCAVATED OR BORROW MATERIAL, 2 MILE ROUND-TRIP, 2.2 LOADS/HR	1	LCY	\$10.50
93410	BACKFILL & COMPACTION, TRENCH 6" TO 12" LIFTS, DOZER BKFL, CMPCT W/ SHEEPSFOOT ROLLER	1	ECY	\$5.20
	BACKFILL & COMPACTION, DOZER BKFL, ROLLER CMPCT IN 12" LAYERS	1	ECY	\$8.40
	BACKFILL & COMPACTION, DOZER BKFL, CMPCT W/ VIBRATING ROLLER	1	ECY	\$4.80

APPENDIX A - SUPPORT FACILITIES UNIT COST TABLE (PART - II, Support Facilities).

NOTE: The Support Fac Unit Costs are for guidance only. Adjustment to these Unit Costs are allowed when local cost data are available with back-ups.

<u>CAT CODE</u>	<u>ITEM</u>	<u>QTY</u>	<u>UNIT</u>	<u>UNIT COST (\$/UNIT)</u>
	BACKFILL & COMPACTION, BY HAND, HEAVY SOIL	1	LCY	\$60.00
93410	DRILLING & BLASTING, HARD ROCK, UPTO 1500 CY, MACHINE DRILL, DEEP HOLE METHOD	1	BCY	\$85.00
	RIP SHALE- MEDIUM HARD, BY 180 H.P REAR RIPPER & LOAD	1	BCY	\$66.00
88040	<u>AT/FP VEHICULAR BARRICADES</u>			
	Barrier Standards			
	SD-STD-02.01 specifies perpendicular barrier impact by a 15,000 lb. (6810 kg) vehicle "K" indicates the Dept of State certified barrier's maximum vehicle impact speed rating "L" indicates the test vehicle's distance of penetration upon impact with barrier			
	K12 = 50 mph (88 kph); L3 = 3'-0" (915 mm) K8 = 40 mph (65 kph) K4 = 30 mph (48 kph)			
	Note: Electrical connection costs are only included up to five feet from the unit. Additional electrical power requirements to be added separately. All active fixed barriers with a remote control panel include costs for barrier installation, safety loop, traffic arm, & traffic lights. Costs for CCTV, Cameras, Alarms, ETC not included.			
	<u>CONCRETE PLANTER - VEHICLE BARRIER</u> , STOPS 4,000 LB VEHICLES AT 40 MPH (K-8 BARRIER)			
88040	CONC PLANTER, ROUND, EXPOSED AGGR FINISH, 36" DIA x 30" HIGH, NO FILL MATERIAL	1	EA	\$957.00
	CONC PLANTER, RECTANGULAR, EXPOSED AGGR FINISH, 96" L x 24" W x 36" H, NO FILL MATERIAL	1	EA	\$1,266.00
	CONC PLANTER, ROUND, EXPOSED AGGR FINISH, 84" DIA x 36" HIGH, NO FILL MATERIAL	1	EA	\$1,913.00
	CONC BARRIER, DECORATIVE GEOMETRIC DESIGN, 96" L x 24" W x 36" H, NO FILL MATERIAL	1	EA	\$1,997.00
	<u>GLASS FIBER REINFORCED CONCRETE SECURITY BARRIERS (GFRC)</u> , STOPS 4,000 LB VEHICLE AT 40 MPH			
88040	CONC FILLED GFRC, DECORATIVE IMPALER, 10' SECTION, INCL SITE PREPRATION ON BARE GROUND	1	EA	\$3,572.00
	CONC FILLED GFRC, DECORATIVE IMPALER, 12' SECTION, INCL SITE PREPRATION ON BARE GROUND	1	EA	\$4,163.00
	GFRC DECORATIVE JERSEY BARRIER COVER, 12' SECTION, EXCL FILLING MATERIALS (SOIL)	1	EA	\$1,800.00
	CONC FILLED PAINTED PIPE BOLLARD, 8' L x 4' D HOLE, 8" DIAMETER	1	EA	\$1,351.00
	<u>CRASH BARRIERS</u> , STOPS 15000 LB VEHICLE @ 50 MPH, INCL ALL LABOR, MATERIAL & EQUIP (LME) FOR COMPLETE INSTALLATION			

APPENDIX A - SUPPORT FACILITIES UNIT COST TABLE (PART - II, Support Facilities).

NOTE: The Support Fac Unit Costs are for guidance only. Adjustment to these Unit Costs are allowed when local cost data are available with back-ups.

<u>CAT CODE</u>	<u>ITEM</u>	<u>QTY</u>	<u>UNIT</u>	<u>UNIT COST (\$/UNIT)</u>
88040	20' WIDE DROP ARM CRASH BARRIER, INCL ALL LME FOR COMPL INSTALLATION	1	EA	\$87,200.00
	24' WIDE DROP ARM CRASH BARRIER, INCL ALL LME FOR COMPL INSTALLATION	1	EA	\$116,450.00
	12' WIDE PORTABLE WEDGE CRASH BARRIER, INCL ALL LME FOR COMPL INSTALLATION	1	EA	\$146,250.00
	20' WIDE SLIDING ROLLER CRASH BARRIER, INCL ALL LME FOR COMPL INSTALLATION	1	EA	\$267,210.00
	20' WIDE SLIDING CANTILEVER CRASH BARRIER, INCL ALL LME FOR COMPL INSTALLATION	1	EA	\$267,210.00
	<u>RAISED BOLLARD CRASH BARRIER</u>, INCL ALL LABOR, MATERIAL & EQUIP (LME) FOR COMPLETE INSTALLATION			
88040	10' WIDE, RAISED BOLLARD CRASH BARRIER, STANDARD POWER, INCL ALL LME FOR COMPL INSTAL	1	EA	\$52,650.00
	12' WIDE, RAISED BOLLARD CRASH BARRIER, STANDARD POWER, INCL ALL LME FOR COMPL INSTAL	1	EA	\$60,190.00
	10' WIDE, RAISED BOLLARD CRASH BARRIER, SOLAR POWER, INCL ALL LME FOR COMPL INSTAL	1	EA	\$64,130.00
	12' WIDE, RAISED BOLLARD CRASH BARRIER, SOLAR POWER, INCL ALL LME FOR COMPL INSTAL	1	EA	\$71,430.00
	INGROUND TIRE SHREDDER, 15' WIDE, INCL ALL LME FOR COMPL INSTALLATION	1	EA	\$56,150.00

**APPENDIX C (UFC 3-700- 01, Table 4-2), PAX Newsletter 3.2.2, dated 20 March 2020
 TRI-SERVICE MILITARY CONSTRUCTION PROGRAM (MCP) INDEX FOR FY 2019-26 PROGRAMS
 Based on Inflation Guidance Published by OUSD (Comptroller), dated 30 April 2019**

<u>FISCAL YEAR (FY)</u>	<u>DATES</u>	<u>INDEX</u>	<u>ESCALATION PERCENTAGE FOR FISCAL YEAR</u>
FY 2019	1-Oct- 2018 -----	2918	----- FY19
	1-Jan- 2019 -----	2933	
	1-Apr- 2019 -----	2947	
	1-Jul- 2019 -----	2962	
FY 2020	1-Oct- 2019 -----	2976	----- FY20 (2.0%)
	1-Jan- 2020 -----	2991	
	1-Apr- 2020 -----	3006	
	1-Jul- 2020 -----	3021	
FY 2021	1-Oct- 2020 -----	3036	----- FY21 (2.0%)
	1-Jan- 2021 -----	3052	
	1-Apr- 2021 -----	3067	
	1-Jul- 2021 -----	3082	
FY 2022	1-Oct- 2021 -----	3097	----- FY22 (2.0%)
	1-Jan- 2022 -----	3113	
	1-Apr- 2022 -----	3128	
	1-Jul- 2022 -----	3144	
FY 2023	1-Oct- 2022 -----	3159	----- FY23 (2.0%)
	1-Jan- 2023 -----	3175	
	1-Apr- 2023 -----	3191	
	1-Jul- 2023 -----	3207	
FY 2024	1-Oct- 2023 -----	3222	----- FY24 (2.0%)
	1-Jan- 2024 -----	3238	
	1-Apr- 2024 -----	3254	
	1-Jul- 2024 -----	3270	
FY 2025	1-Oct- 2024 -----	3286	----- FY25 (2.0%)
	1-Jan- 2025 -----	3303	
	1-Apr- 2025 -----	3319	
	1-Jul- 2025 -----	3336	
FY 2026	1-Oct- 2025 -----	3352	----- FY26 (2.0%)
	1-Jan- 2026 -----		

NOTES:

1. Use **2.0%** per fiscal year for projection beyond **FY 2024**
2. Tri - Service MCP Index (1,000) = 1 October 1979 ENR Historical Building Cost Index (1,900)
3. The MCP indexes after 1 Oct 2018 were derived using the Price Escalation Indices (Annual Rates in Percentages) for Budget Authority published in the 30 April 2019 Inflation Guidance - Fiscal Year (FY) 2021 President's Budget.
4. This revised index table supersedes the MCP index table published as Appendix-C to PAX Newsletter 3.2.2, dated **30 May 2019**

TABLE I - SIZE ADJUSTMENT FACTORS
PART I - BUILDING (OTHER THAN BARRACKS & FAMILY HOUSING)

<u>SIZE RATIO</u>	<u>ADJUST FACTOR</u>						
< 0.05	1.2750	0.9000	1.0110	1.8000	0.9490	2.7000	0.9250
0.0500	1.2750	0.9500	1.0050	1.8500	0.9470	2.7500	0.9240
0.1000	1.2690	1.0000	1.0000	1.9000	0.9450	2.8000	0.9240
0.1500	1.2320	1.0500	0.9950	1.9500	0.9430	2.8500	0.9230
0.2000	1.2020	1.1000	0.9900	2.0000	0.9420	2.9000	0.9220
0.2500	1.1750	1.1500	0.9860	2.0500	0.9400	2.9500	0.9210
0.3000	1.1520	1.2000	0.9820	2.1000	0.9390	3.0000	0.9210
0.3500	1.1320	1.2500	0.9780	2.1500	0.9370	3.0500	0.9200
0.4000	1.1140	1.3000	0.9740	2.2000	0.9360	>3.05	0.9200
0.4500	1.0980	1.3500	0.9710	2.2500	0.9350		
0.5000	1.0840	1.4000	0.9680	2.3000	0.9330		
0.5500	1.0720	1.4500	0.9650	2.3500	0.9320		
0.6000	1.0600	1.5000	0.9620	2.4000	0.9310		
0.6500	1.0500	1.5500	0.9600	2.4500	0.9300		
0.7000	1.0410	1.6000	0.9570	2.5000	0.9290		
0.7500	1.0330	1.6500	0.9550	2.5500	0.9280		
0.8000	1.0250	1.7000	0.9530	2.6000	0.9270		
0.8500	1.0180	1.7500	0.9510	2.6500	0.9260		

NOTE: Size ratio is determined by dividing the proposed building size by the average size shown in Part I of Appendix A. To determine the size adjustment factor, use the closest size ratio from above table.

PART II - PROJECT SIZE ADJUSTMENTS FOR BARRACKS/FAMILY

MILITARY FAMILY HOUSING PROJECT SIZE ADJUSTMENT FACTORS		BARRACKS/ DORMITORIES PROJECT SIZE ADJUSTMENT FACTORS	
NUMBER OF UNITS in the project	PROJECT SIZE FACTOR	NUMBER OF ROOMS in the project	PROJECT SIZE FACTOR
1-9	1.25	1-99	1.07
10-19	1.15	100-149	1.03
20-49	1.10	150-199	1.00
50-99	1.04	200-299	0.97
100-199	1.00	300+	0.95
200-299	0.93		
300+	0.90		

CHART C, METRIC/ENGLISH SYSTEMS

QUANTITY	FROM			TO OBTAIN	
LENGTH	inch		25.400000	millimeter	
	foot		0.304800	meter	
	yard		0.914400	meter	
	mile (U.S. Status)		1.609344	kilometer	
	millimeter		0.039370	inch	
	meter		3.280840	foot	
	meter		1.093613	yard	
	kilometer		0.621370	mile	
AREA	square inch		645.160300	square millimeter	
	square foot		0.092903	square meter	
	square yard		0.836127	square meter	
	square mile		2.589998	square kilometer	
	acre		4046.873000	square meter	
	acre		0.404687	hectare	
	square millimeter		0.001550	square inch	
	square meter		10.763910	square foot	
	square meter		1.195990	square yard	
	square kilometer		0.386101	square mile	
	square meter		0.000247	acre	
	hectare		2.471044	acre	
VOLUME	cubic inch		16387.060000	cubic millimeter	
	cubic foot		0.028316	cubic meter	
	cubic yard		0.764555	cubic meter	
	gallon (U.S. liquid)		3.785412	liter	
	quart (U.S. liquid)		0.946353	liter	
	cubic millimeter		0.000061	cubic inch	
	cubic meter		35.314662	cubic foot	
	cubic meter		1.307951	cubic yard	
	liter		0.264172	gallon	
	liter		1.056688	quart	
MASS	ounce (avoirdupois)		28.349520	gram	
	pound (avoirdupois)		0.453592	kilogram	
	short ton		907.185000	kilogram	
	gram		0.035273	ounce	
	kilogram		2.204622	pound	
	kilogram		0.001102	short ton	
ENERGY -					
HEAT &	kilowatthour		3.600000	megajoule	
WORK	btu		1.055056	kilojoule	
	horsepower hour		2.684520	megajoule	
	megajoule		0.277780	kilowatthour	
	kilojoule		0.947817	btu	
	megajoule		0.372506	horsepower hour	
POWER	ton (refrigeration)		3.517000	kw	
	btu/s		1.055056	kw	
	hp (electric)		745.700000	w	
	btu/h		0.293071	w	
	kw		0.284333	ton (refrigeration)	
	kw		0.947817	btu/s	
	w		0.001341	hp (electric)	
	w		3.412141	btu/h	